

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22506-00-00
Spot: CNWNWNW Sec/Twnshp/Rge: 10-7S-20W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: PROBASCO Well Number: 7-4
County: ROOKS Total Vertical Depth: 3625 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 205 160 SX CMT
Production: Size 4.5 feet: 3620 200 SX CMT \$117.81
Liner: Size feet:

Well Type: FOR OIL ^{rec up} UIC Docket No: Date/Time to Plug: 10/04/2001 9:00 AM

Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC

Proposal Rcvd. from: JAMES B. DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/04/2001 10:00 AM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

4 1/2" casing - squeezed down 25 sxs 60/40 pozmix - 10% gel with 300# hulls, followed with 8 sxs gel, followed with 125 sxs cement with 100# hulls.
Max. P.S.I. 800#.
8 5/8" S.P. Cement to surface.

Remarks: LEASE FORMERLY KNOWN AS PROBASCO #A-4. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

RECEIVED

(TECHNICIAN)

INVOICED

OCT 16 2001

DATE 10-16-01

Form CP-2/3

KCC WICHITA

INV. NO. 2002060810

OCT 09 2001

REPLACEMENT CARD

FRONTIER OIL COMPANY
 1720 KSB&T BLDG.
 WICHITA, KS. 67202


#4 'A' PROBASCO

10-7-20W
 NW NW NW

CONTR RED TIGER DRILLING CTY ROOKS

GEOL RICHARD PARKER FIELD PROBASCO

ELV 2109 KB SPD 10/6/84 CARD ISSUED 1/3/85 IP P 118.20 BO &
2104 GL DRLG COMP 10/14/84 78.80 BWPD
 API 15-163-22,506 LKC 3369-3501 OA



SMP	Tops	Depth/Datum
ANH	1672+ 437
TOP	3090- 981
HEEB	3292-1183
TOR	3316-1207
LANS	3330-1221
BKC	3535-1426
CHTY CONG	3573-1464
ARB	3611-1502
RTD	3625-1516

8 5/8 " 205 / 160SX, 5 1/2 " 3620 / 200SX

DST (1) 3354-3374 (LANS) / 60-30-60-30, 1080' GIP, REC 1890' CLEAN GSY OIL, SIP 1128-1128#, FP 90-520 / 554-694#

DST (2) 3374-3418 (LANS) / 60-30-60-30, REC 90' M, 620' MSW, SIP 948-903#, FP 90-226 / 226-384#

DST (3) 3468-3486 (LKC) / 60-30-60-30, 1120' GIP, REC 1650' CLEAN GSY OIL, SIP 681-655#, FP 113-486 / 542-610#

DST (4) 3488-3508 (LKC) / 15-30-0-0, 420' GIP, REC 90' CLEAN GSY OIL, 90' MC GSY OIL, ISIP 768#, IFP 45-102#

DST (5) 3520-3570 (KC) / 30-30-30-30, REC 10' M; SIP 193-113#, FP 57-57 / 57-57#

MICT - CO, PF (LKC) 3369-3374, W / 4 SPF, AC 500 GAL (15% REG), SWB DWN, SO, PF (LKC) 3480-3486, W / 4 SPF, AC 500 GAL (15% REG), SWB DWN, SO, PF (LKC) 3485-3501, W / 4 SPF, AC 500 GAL (15% REG), SWB DWN, SO, SET 2 3/8 " TBG AT 3540', POP, P 118.20 BO & 78.80 BWPD (GR 36.5%), 10/25/84

INFO RELEASED: 2/27/86 - WAS OIL WELL - TIGHT HOLE