

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20382-00-00
Spot: N2N2NW Sec/Twnshp/Rge: 28-12S-33W
4950 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HUEFTLE Well #: 4
County: LOGAN Total Vertical Depth: 4740 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comment
PLG1		4211		
PROD	4.5	4740	0	250 SX CMT
SURF	8.625	307	0	200 SX CMT

154⁰⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2005 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RICHARD L WALLGREN SR Company: HANSEN, DANE G. TRUST Phone: (785) 689-4816

Proposed Plugging Method: Ordered 300 sxs 60/40 poxmix - 10% gel and 800# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2005 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 307' w/200 sxs cement.
4 1/2" production casing set at 4740' w/250 sxs cement.
PBTD 4211' with CIBP. TD 4740'.
Ran tubing to 2500' - pumped 125 sxs cement with 500# hulls.
Pulled tubing to 1300' - pumped 40 sxs cement - cement to surface.
Pulled tubing to surface. Connected to 4 1/2" production casing - pumped 30 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
Connected to 8 5/8" surface casing - pumped 10 sxs cement.
Max. P.S.I. 400#. S.I.P. #150#.

Perfs:

Top	Bot	Thru	Comments
4659	4662		
4652	4655		
4638	4641		
4548	4552		
4318	4324		
4290	4294		
4237	4240		
4223	4226		

Remarks: ALLIED CEMENTING COMPANY-TICKET #21655.

Plugged through: TBG

INVOICED
DATE 11-18-05
WF. NO. 2006060743

District: 04

Signed

Darrel Dipman
(TECHNICIAN)

RECEIVED

NOV 17 2005

KCC WICHITA

Form CP-2/3

NOV 02 2005


THE DANE G. HANSEN TRUST
 P.O. BOX 187
 LOGAN, KS. 67646

#4 HUEFTLE

28-12-33W
 C. N/2 N/2 NW

CONTR GALLOWAY DRILLING CTY LOGAN

GEOLOGICAL JIM GRIBI FIELD OWEN WEST



ELV 3137 KB SPD 6/28/85 CARD ISSUED 12/12/85 IP P 12 BO & 72 RWPP
3132 GL DRLG COMP 7/9/85 KC 4223-324 OA
 API 15-109-20,382 MARM 4548-4552

LOG	Tops	Depth/Datum
ANH	2612+	525
B/ANH	2634+	503
WAB	3682-	545
TOP	3810-	673
HEEB	4035-	898
TOR	4058-	921
LANS	4076-	939
MUN CR	4219-	1082
STARK SH	4306-	1169
BKC	4370-	1233
MARM	4411-	1274
PAW	4504-	1367
FT SC	4562-	1425
CHER SH	4590-	1453

8 5/8 " 307 / 200SX, 4 1/2 " 4740 / 230SX
 DST (1) 4032-82 (TOR) / 15-45-60-45, REC 120' SOCMW, 120'
 OIL SPTD MW, SIP 1177-1135#, FP 41-41 / 72-119#
 DST (2) 4148-64 (KC) / 15-45-60-45, REC 30' OIL SPTD MW,
 300' SW, SIP 1230-1198#, FP 41-41 / 72-145#
 DST (3) 4219-50 (KC) / 15-45-15-45, 40' GIP, REC 20' MCO, SIP
 812-802#, FP 41-41 / 67-67#
 DST (4) 4252-84 (KC) / 15-45-30-45, REC 15' OIL & GCWM, 60'
 SO & GCWM, SIP 239-239#, FP 41-41 / 62-62#
 DST (5) 4281-4330 (KC) / 15-45-15-45, REC 10' OIL SPTD M,
 60' M, SIP 963-963#, FP 41-41 / 57-57#
 JOHN ZN 4634-1497 RTD 4740-1603
 MISS 4729-1592 LTD 4742-1605

NOTICED

(over)