

10-18-87

163-22,954-00-00

6 040825

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NE NW SE, SEC. 7, T. 7 S, R. 20
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6111

Operator: N B Company Inc.
Name & Address: P.O. Box 506
Russell, Kansas 67665

Lease Name LeSage Well # 1
County Rooks 118.63
Well Total Depth 3650 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 200 cwc

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number

Address Russell, Kansas

Company to plug at: Hour: 5:00 PM Day: 18 Month: Oct Year: 19 87

Plugging proposal received from Emphasis Daylite Driller

(company name) Emphasis (phone)

were: Order 215 sks 60/40 Pozmix 6% Gel 3% Cal Cl 1sk Flocele and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 5:00 PM Day: 18 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT

1st plug at 3650' w/25 sks

2nd plug at 1650' w/25 sks

3rd plug at 1100' w/100 sks

4th plug at 225' w/40 sks

5th plug at 40' w/10 sks

Remarks: 15 sks in rat hole.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If desired, please observe this plugging.)

DATE 1-7-88

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 19292

Dennis L. Hamel

FORM CP-2/3 LR Rev. 01-84

RECEIVED
12-16-1987
WICHITA, KANSAS