

6 040324

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,628-00-00

SE NW SESEC. 11, T 7 S, R 20 W/X

1650 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9321

Lease Name Sammons Well # 1

Operator: Circle G Oil

County Rooks 117.65

Name & Address R.R.

Well Total Depth 3620 feet

Logan, Ks. 67646

Conductor Pipe: Size 0 feet ✓

Surface Casing: Size 8^{5/8} feet 252 w/155

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXX

Other well as hereinafter indicated _____

Plugging Contractor R&C Drilling License Number 9087

Address Hays, Ks.

Company to plug at: Hour: PM Day: 20 Month: February Year: 19 85

Plugging proposal received from John Wise

(company name) R&C Drilling (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 2 sk hulls and 8^{5/8}"

plug. Spot with drill pipe with no less than 36 vis. mud between all plugs,
with good circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 12:45PM Day: 20 Month: February Year: 19 85

ACTUAL PLUGGING REPORT

1st plug @ 1700 w/40 sks

2nd plug @ 1000 w/100 sks w/2 sks hulls

3rd plug @ 260 w/40 sks

4th plug @ 40 w/10 sks (solid bridge)

10 sks in Rat Hole

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 2-26-85

INV. NO. 7130

Signed Dennis L. Hamel
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
02-25-1985
FEB 25 1985
CONSERVATION DIVISION
Wichita, Kansas

2-22-85