

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21533-00-00  
Spot: W2E2W2 Sec/Twnshp/Rge: 21-20S-19W  
2640 feet from S Section Line, 1600 feet from W Section Line  
Lease Name: SMITH Well #: 3  
County: PAWNEE Total Vertical Depth: 4351 feet

Operator License No.: 30420  
Op Name: INNONE, VINCENT DBA V.J.I. NATURA  
Address: 30-38 48TH STREET  
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	658		

#141<sup>41</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/08/2005 4:00 PM  
Plug Co. License No.: 33436 Plug Co. Name: FORREST ENERGY LIMITED LIABILITY CO  
Proposal Rcvd. from: GILBERT SMITH Company: FORREST ENERGY LIMITED LIABI Phone: (620) 665-6088

Proposed Plugging Method: 1ST PLUG AT 1200' WITH 40 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 11/08/2005 6:10 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1200' WITH 40 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.


Perfs:

RECEIVED  
NOV 18 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ACID SERVICE.

Plugged through: DP

District: 01



Signed

Michael Maier  
(TECHNICIAN)

INVOICED  
DATE 11-18-05  
INV. NO 2006060751

Form CR-2/5