

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20601-00-00
Spot: NWSENV Sec/Twnshp/Rge: 5-17S-32W
1860 feet from N Section Line, 1718 feet from W Section Line
Lease Name: ADELE Well #: 1
County: SCOTT Total Vertical Depth: 4759 feet

Operator License No.: 33518
Op Name: COLEMAN PRODUCTION, LLC
Address: RT 2 BOX 119
STROUD, OK 74079

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4175		WITH 2 SX CMT
PC		1600		NOT CEMENTED
PROD	4.5	4436	870	WITH 150 SX CMT
SURF	8.625	261		180 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/10/2005 1:00 PM
Plug Co. License No.: 33518 Plug Co. Name: COLEMAN PRODUCTION, LLC
Proposal Rcvd. from: JIM COLEMAN Company: COLEMAN PRODUCTION, LLC Phone: (918) 968-5398

Proposed Plugging Method: 1ST PLUG CIBP WITH 2 SX CMT 50' ABOVE TOP PERF. 2ND PLUG EITHER 50 SX CMT VIA CASING OR CIBP @ 2350' WITH 2 SX CMT. 3RD PLUG AT 1600' WITH 80 SX CMT. 4TH PLUG AT 850' WITH 50 SX CMT. 5TH PLUG AT 290' WITH 50 SX CMT. 6TH PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2005 4:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG SET CIBP @ 4175' WITH 2 SX CMT. SHOOT CASING AT 2600' & DID NOT COME LOOSE. SHOT CASING AT 1730' & DID NOT COME LOOSE. 2ND PLUG SET CIBP @ 1750' & PUMPED 100 SX CMT. SHOT CASING AT 870' & CAME LOOSE. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG PULLED TO 290' & PUMPED 50 SX CMT. 5TH PLUG TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4355	4363		
4301	4311		
4284	4292		
4277	4281		
4225	4229		
4187	4195		

RECEIVED
NOV 18 2005
KCC WICHITA


INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

DATE 11-18-05
INV. NO 2006060753

District: 01



Signed

Michael J. Maier
(TECHNICIAN)