

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

RECEIVED  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1989

WELL PLUGGING APPLICATION FORM  
(File One Copy)

JAN 23 1989

CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER 15-163-21,609-00-00 (of this well) 6/89  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Damson Oil Corporation OPERATORS LICENSE NO. 08098

ADDRESS 3300 N "A" Bldg 8, Suite 100 Midland, TX 79705 PHONE # (915) 687-0455

LEASE (FARM) Reichard Byfield WELL NO. 1 WELL LOCATION NW NW NE COUNTY Rooks

SEC. 19 TWP. 7S RGE. 17 (E) or (W) TOTAL DEPTH 3315 PLUG BACK TD 3292

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 1175' CEMENTED WITH 500 SACKS

CASING SIZE 5-1/2" SET AT 3315' CEMENTED WITH 150 SACKS

PERFORATED AT 3258-3259-3263-3264' 1 shot each

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL SEE BACK OF FORM

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Prior to April 1, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Fred Simondi PHONE # (405) 254-3818

ADDRESS 3311 22nd St. Apt 228 Woodward, OK 73801

PLUGGING CONTRACTOR  Halliburton Services LICENSE NO. \_\_\_\_\_

ADDRESS \_\_\_\_\_ PHONE # ( ) \_\_\_\_\_

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: A.W. Humphrey  
(Operator or Agent)

JAN 9 1989

DATE: 1-5-89

Hays, KS

(4)

WORKOVER PROGNOSIS

LEASE/WELL: REICHARD-BYFIELD 1

FIELD: RIFFE

LOCATION: 535' FNL 2450' FEL SEC 19 T7S R17W

CURRENT TEST: SHUT-IN

OBJECTIVES: PLUG AND ABANDON WELL

JUSTIFICATION: WELL IS UNECONOMIC TO PRODUCE AT CURRENT RATE

WELL DATA: 13 5/8 54.5# CONDUCTOR @92' CMT W/120 SX CMT CMT CIRC.  
8 5/8 CASING @1175' CMT W/500 SX CMT TOP OF CMT CIRCULATED  
5 1/2 CASING @3315' CMT W/150 SX CMT TOP @2635'

RECOMMENDED PROCEDURE

1. RUPU. PULL RODS. LOWER TBG. TAG BOTTOM
2. PULL AND LAY DOWN ALL TBG. RDPU
3. RU CEMENTERS ON 5 1/2 CSG. MIX AND PUMP VOLUME EQUAL TO CAPACITY OF CASING PLUS 25% EXCESS USING 65/35 POZ W/10% GEL & 2% ECONOLITE ADDITIVES W/500# COTTONSEED HULLS IN 1ST 20 BBLs OF SLURRY (MAY WANT TO TAIL IN W/25 SX NEAT CMT). FILL COMPLETELY W/CMT.
4. RU ON 5 1/2 X 8 5/8 ANNULUS AND PUMP CAPACITY TO FILL ANNULUS W/CMT.
5. CHECK 8 5/8 AND 13 3/8 ANNULUS. FILL W/CMT IF NOT ALREADY FULL. CUT OFF WELLHEAD 5' BELOW GROUND LEVEL AND WELD ON PLATE. RECLAIM WELL LOCATION.
6. REMOVE ALL EQUIPMENT AS DIRECTED BY DISTRICT OFFICE

State of Kansas



15-163-21609-00-00

Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

January 24, 1989

APR 24 1989

WELL PLUGGING NOTICE

EXPIRES

Reichard Byfield #1  
NW NW NE  
Sec. 19-07S-17W  
Rooks County

Damson Oil Corporation  
3300 N "A" Bldg. 8, Ste. 100  
Midland, TX 79705


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #4 2301 E: 13th, Hays, KS 67601 (913) 628-1200