


15-163-02634-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rooks County. Sec. 18 Twp. 7S Rge. 20W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NW NE

Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Le Sage Well No. 2  
Office Address 780 Fourth National Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 11, 1960  
Application for plugging filed November 11, 1960  
Application for plugging approved November 11, 1960  
Plugging commenced November 11, 1960  
Plugging completed November 11, 1960  
Reason for abandonment of well or producing formation No commercial quantities  
of oil found.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3673 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	190'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 550 feet with  
20 sacks of cement; Set second  
plug at 185 feet with 15 sacks of  
cement; Set top plug at 40 feet  
with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Imperial Oil of Kansas, Inc. 12-2-60  
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
R. L. BACON (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.  
By: R. L. Bacon  
(Signature) 780 Fourth National Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of December, 1960  
Mona L. Latier  
Mona L. Latier Notary Public.  
My commission expires July 7, 1962



15-103-02634-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
780 Fourth National Bldg.  
Wichita 2, Kansas

Le Sage #2  
C NW NE Sec. 18-7S-20W  
Rooks County, Kansas

Total Depth: 3673'

Elevation: 2143' K.B.  
Production: D & A

Commenced: 11-1-60 Completed: 11-11-60

Contractor: Imperial Oil of Kansas, Inc.  
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 190' with 150 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Clay & Sand	190'	Topeka	3133' (- 990)
Shale & Shells	630'	Heebner	3338' (-1195)
Shale & Sand	1230'	Toronto	3360' (-1217)
Dakota Sand	1440'	Lansing	3376' (-1233)
Shale & Redbed	1705'	Base/Kansas City	3575' (-1432)
Shale & Shells	1720'	Marmaton lime	3610' (-1467)
Anhydrite	1752'	Arbuckle	3648' (-1505)
Shale & Shells	2180'	Rotary Total Depth	3673' (-1530)
Shale & Lime	3305'		
Lime	3673'		
Total Depth	3673'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the Daily Drilling Reports.

IMPERIAL OIL OF KANSAS, INC.

By: R. L. Bacon  
R. L. Bacon - Vice-Pres.

Subscribed and sworn to before me this 17th day of November, 1960.

My Commission Expires:

July 7, 1962

**RECEIVED**  
STATE CORPORATION COMMISSION

Mona L. Latier  
Mona L. Latier - Notary Public

DEC 2 1960  
CONSERVATION DIVISION  
Wichita, Kansas

12-2-60