


15-163-01153-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rooks County. Sec. 18 Twp. 7S Rge. 20W (E) (W)
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines NE NE SE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Trarbach Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 13 1960
Application for plugging filed October 13 1960
Application for plugging approved October 13 1960
Plugging commenced October 13 1960
Plugging completed October 13 1960
Reason for abandonment of well or producing formation No commercial quantities of oil found.



Locate well correctly on above Section Plat


If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3705 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	191'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 550 feet with 20 sacks of cement;
Set second plug at 185 feet with 15 sacks of cement;
Set top plug at 40 feet with 10 sacks of cement.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc. 11-4-60
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. L. Bacon (employee of ~~owner~~ owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: R. L. Bacon Vice-Pres.
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 60

Moral L. Laker
Notary Public.

My commission expires July 7, 1962



DRILLER'S LOG

RECEIVED
STATE COMMISSION

NOV 4 1960

CONSERVATION DIVISION
Wichita, Kansas

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.
Wichita 2, Kansas

15-163-01153-00-00

11-4-60

Trarbach No. 1
NE NE SE Sec. 18-7S-20W
Rooks County, Kansas

Total Depth: 3705'

Commenced: 10-1-60 Completed: 10-13-60

Elevation: 2091' K.B.
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 191' with 150 sacks of cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Sand & Rock	50'	Topeka	3070' (- 979)
Surface Clay & Sand	193'	Heebner	3275' (-1184)
Shale, Shells & Sand	1015'	Toronto	3295' (-1204)
Shale & Shells	1170'	Lansing	3312' (-1221)
Dakota Sand	1390'	Base/Kansas City	3511' (-1420)
Shale & Redbed	1662'	Marmaton limestone	3543' (-1452)
Anhydrite	1692'	Conglomerate	3550' (-1459)
Shale & Shells	1750'	Arbuckle	3556' (-1465)
Shale & Lime	3327'	Granite	3702' (-1611)
Lime	3550'	Rotary Total Depth	3705' (-1614)
Lime & Arbuckle	3560'		
Lime	3577'		
Arbuckle	3592'		
Lime & Arbuckle	3705'		
Total Depth	3705'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: R. L. Bacon
R. L. Bacon - Vice-Pres.

Subscribed and sworn to before me this 21st day of October, 1960.

My Commission Expires:

July 7, 1962

Mona L. Latier
Mona L. Latier - Notary Public