


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-163-01154-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Rooks \_\_\_\_\_ County. Sec. 18 Twp. 7S Rge. 20W (E) \_\_\_\_\_ (W) \_\_\_\_\_

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines. C NE SW

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Trarbach "B" Well No. 1

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 11, 1960

Application for plugging filed December 11, 1960

Application for plugging approved December 11, 1960

Plugging commenced December 11, 1960

Plugging completed December 11, 1960

Reason for abandonment of well or producing formation No commercial quantities

of oil found.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3601 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	188'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 550 feet with 20 sacks of cement; Set second plug at 185 feet with 20 sacks of cement; Set top plug at 40 feet with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 29 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Imperial Oil of Kansas, Inc. 12-29-60  
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
R. L. Bacon (employee of ~~owner~~ ~~operator~~ ~~owner~~ ~~operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

By: R L Bacon V-P  
(Signature)  
780 Fourth National Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 19 60

My commission expires October 12, 1964

Cecilia C. Klug  
Cecilia C. Klug Notary Public.

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
780 Fourth National Building  
Wichita, Kansas

15-163-01134-00-00

Trarbach B-1  
C NE SW Sec. 18-7-20W  
Rooks County, Kansas

Total Depth: 3601

Commenced: 12-2-60 Completed: 12-11-60

Elevation: 2121 KB  
Production: Dry

Contractor: Imerial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 188' with 175 sacks cement.

Figures indicate bottom of formations:

Surface Clay & Sand	187'
Shale & Shells	640'
Shale & Sand	1198'
Dakota Sand	1432'
Shale & Red Bed	1700'
Shale & Shells	1724'
Anhydrite	1750'
Shale & Shells	2175'
Lime & Shale	3280'
Lime	3573'
Lime "Arbuckle"	3601'
Total Depth	3601'

(Sample)	<u>TOPS</u>
Topeka	3110 (- 989)
Heebner	3312 (-1191)
Toronto	3333 (-1212)
Lansing	3348 (-1227)
B/Kansas City	3544 (-1423)
Mamaton Lime	3577 (-1456)
Arbuckle	3583 (-1462)
Total Depth	3601 (-1480)

We hereby certify this to be a correct and accurate log of the above described well, according to the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By Raymond L. Bacon  
Raymond L. Bacon

Subscribed and sworn to before me this 22nd day of December, 1960.

My Commission Expires:

October 12, 1964

Cecilia C. Klug  
Cecilia C. Klug, Notary Public

RECEIVED  
STATE CORPORATE COMMISSION

DEC 29 1960  
CONSERVATION DIVISION  
Wichita, Kansas

12-29-60