


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-163-02632-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks County. Sec. 7 Twp. 7S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SW  
Lease Owner: Imperial Oil of Kansas, Inc.  
Lease Name Western Auto Well No. 2  
Office Address 780 Fourth National Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 16, 1961  
Application for plugging filed January 16, 1961  
Application for plugging approved January 16, 1961  
Plugging commenced January 16, 1961  
Plugging completed January 16, 1961  
Reason for abandonment of well or producing formation No commercial quantities of oil found.  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3635 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	188'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 550 feet with  
20 sacks of cement; Set second  
plug at 185 feet with 15 sacks  
of cement; Set top plug at  
40 feet with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 6 1961  
02-06-1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Imperial Oil of Kansas, Inc.  
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
R. L. Bacon (employee of ~~owner~~ or ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: R. L. Bacon V-P  
780 Fourth National Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1961

My commission expires October 12, 1964  
Cecilia C. Klug Notary Public.



RECEIVED  
STATE CORPORATION COMMISSION

FEB 6 1961

CONSERVATION DIVISION  
Wichita, Kansas

*AL*

DRILLER'S LOG

15-163-02632-00-00

Imperial Oil of Kansas, Inc.  
780 Fourth National Building  
Wichita 2, Kansas

Western Auto No. 2  
C NE SW Sec. 7-7-20W  
Rooks County, Kansas

Total Depth: 3635

Elevation: 2151 R.B.  
Production: Dry

Commenced: 1-6-61 Completed: 1-16-61

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" surface pipe at 188' with 150 sacks of cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	(Sample)
Surface Clay & Shale	188'	Topeka	3149 (- 998)
Shale, Sand & Shells	870'	Heebner	3350 (-1199)
Shale & Sand	1240'	Toronto	3371 (-1220)
Dakota Sand	1455'	Lansing	3387 (-1236)
Red Bed & Shale	1724'	Base Kansas City	3582 (-1431)
Anhydrite	1758'	Arbuckle	3620 (-1469)
Shale & Shells	1845'	Total Depth	3635 (-1484)
Shale & Lime	3223'		
Lime	3635'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By Raymond L. Bacon  
Raymond L. Bacon

Subscribed and sworn to before me this 20th day of January, 1961.

My Commission Expires:

October 12, 1964

RECEIVED  
STATE CORPORATION COMMISSION

FEB 6 1961

CONSERVATION DIVISION  
Wichita, Kansas

Cecilia C. Klug  
Cecilia C. Klug, Notary Public