

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-22970-00-00

LEASE NAME Waller

WELL NUMBER 2

4290 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 6 TWP. 7S RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 1/3/88

Plugging Commenced 6/3/88

Plugging Completed 6/5/88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR PanCanadian Petroleum Company

ADDRESS P.O. Box 929, Denver, CO 80201

PHONE#(303) 825-8371 OPERATORS LICENSE NO. 8000

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Attached If not, is well log attached? Yes

Producing Formation Lansing/KC Depth to Top 3546 Bottom 3639 T.D. 3779.50'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/KC	Oil & water	0	314	8 5/8	314'	Cemented in place
		0	3779	4 1/2	3780'	Recovered 2840'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set.

CIBP @ 3400' dump bail 4 sxs cmt on top. Run tubing and fill casing w/drlg mud. Cut casing @ 2840' KB and recover same.

Rig up to 8 5/8" casing & pump 200 sxs B.J. Thrifty mix down casing. Cut casing 6' below surface & weld plate on 8 5/8" casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Eagle Well Service

Address P.O. Box 95 Zurich 67676

STATE OF Kansas COUNTY OF Rooks, ss.

Forrest M. Moore

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Forrest M. Moore

(Address) P.O. Box 929, Denver, CO

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1988

Notary Public

My Commission Expires: March 18, 1991

RECEIVED 04322  
 STATE CORPORATION COMMISSION  
 JUN 10 1988  
 06-10-1988