

15-163-22056-00-01
copy to KCC & D.C.
JL



HELMERICH & PAYNE, INC. UTICA AT TWENTY-FIRST • TULSA, OKLAHOMA 74114

KANSAS DISTRICT
PRODUCTION DEPARTMENT

REPLY TO: P.O. BOX 558
GARDEN CITY, KANSAS 67846

MILLARD L. LINDSAY
District Production Manager

June 5, 1985

Department of Health and Environment
Forbes Field
Topeka, KS 66620
Attn: Susan Hargadine

Dear Susan:

As requested, I am sending completion records on Liebenau 2A SWD NE/4 19-7S-17W, Rooks County, KS, Docket No. 23,829.

Arbuckle perforations at 3028-3034 and Kansas City perforations at 2930-2935 were squeezed with 225 sacks 50/50 pozmix and 75 sacks C1 A. The 8⁵/₈ was squeezed with 150 sacks 50/50 pozmix. Cement was drilled out. Shoe was drilled out at 3280'. Open hole was drilled to 3508'; open hole was acidized with 1000 gallons 15% HCl.

A Baker Model G packer was run on 103 joints 2⁷/₈" fiberglass lined tubing and set at 3216'. Annulus was flushed and filled with 85 barrels fresh water containing KW-37 and XC-320.

Well was put into operation on 1 June 1985 taking 1400 barrels water per day on 24" vacuum.

Sincerely,

Millard L. Lindsay
Millard L. Lindsay
District Production Manager

RECEIVED

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1985

CONSERVATION DIVISION
Wichita Kansas

JUN 07 1985

BUREAU OF OIL FIELD &
ENVIRONMENTAL GEOLOGY

MLL:sp