

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 065-23103-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 10-19-05.

Well Operator: American Warrior, Inc. KCC License #: 4058
(Owner / Company Name) (Operator's)

Address: PO Box 399 City: Garden City

State: KS Zip Code: 67846-0399 Contact Phone: (620) 275 - 9231

Lease: Newell Well #: 1 - 11 Sec. 11 Twp. 9 S. R. 21 East West

App - NE - SW - NW Spot Location / QQQQ County: Graham

1550 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1080 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 207 Cemented with: 160 Sacks

Production Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 2196/2201 (G.L. / K.B.) T.D.: 3800' PBDT: _____ Anhydrite Depth: 1668
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Spot 25 sx of cement @ 3750'. Fill hole with rotary mud to 1660' and spot 25 sx of cement. Filled hole with rotary mud to 950' and spot 100 sx of cement. Fill hole with rotary mud to 250' and spot 40 sx of cement. Fill hole with rotary mud to 40' and spot 10 sx of cement. Put 15 sx in the rathole.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Cecil O'Brate

Phone: (620) 275 - 9231

Address: PO Box 399 City / State: Garden City KS 67846-0399

Plugging Contractor: Berentz Drilling Company, Inc. KCC License #: 5892
(Company Name) (Contractor's)

Address: PO Box 782228 Wichita KS 67278-2228 Phone: (316) 685 - 5908

Proposed Date and Hour of Plugging (if known?): 10-27-05 at 8:00 a.m. Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11-9-05 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 08 2005
KCC WICHITA

11/06

6/06