

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20863-00-00
Spot: NENESW Sec/Twnshp/Rge: 33-29S-33W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PREEDY Well #: 1-33
County: HASKELL Total Vertical Depth: 5645 feet

Operator License No.: 9953
Op Name: HARRIS OIL & GAS COMPANY
Address: 1125 17TH STREET, STE 2290
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4988		
COND	13.38	483		WITH 305 SX CMT
PROD	4.5	5194	1650	WITH 330 SX CMT
SURF	8.625	1575		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2005 10:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RICKY Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: PUMP 200# HULLS WITH 30 SX CMT. PLUG AT 1625' WITH 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2005 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

11/9/05: PUMP 200# HULLS WITH 30 SX CMT. DISPLACE WITH MUD TO PERFS. PRESSURED TO 500# & SHUT IN. 1ST PLUG PULL TO 1620'. CIRCULATE HOLE & PUMP 50 SX CMT. SDON. 11/10/05: 2ND PLUG AT 700' WITH 40 SX CMT. 3RD PLUG AT 80' WITH 25 SX CMT.


Perfs:

Top	Bot	Thru	Comments
5076	5170		
4791	4801		

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

RECEIVED
NOV 22 2005
KCC WICHITA

INVOICED
DATE 11.22.05
INV. NO. 2006060776

FORM CP 512