

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-32021-00-01  
Spot: NWNESW Sec/Twnshp/Rge: 30-18S-7W  
2310 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: MEYER OWWO Well #: 2  
County: RICE Total Vertical Depth: 3189 feet

Operator License No.: 8917  
Op Name: GUSTUS, DEAN DBA JD PRODUCTION  
Address: 701 MAIN  
GENESEO, KS 67444

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3179		
SURF	10.75	198		

#103<sup>64</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2005 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed  
Plugging  
Method:

See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/31/2005 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Tubing stuck and rods parted at 1275'. Able to pull 1500' of tubing. Ran tubing to approximately 1600' and pumped 25 sacks of cement. Pulled tubing to 1050', perforated through tubing, and pumped 50 sacks of cement. Pulled tubing to 700', perforated, and pumped 50 sacks of cement. Pulled tubing to 250', perforated, and circulated cement to surface.

60/40 posmix with 4% gel

Copeland Cement #26532  
Log Tech Perforation #4320

Perfs:

RECEIVED  
KCC DISTRICT #2  
NOV - 8 2005  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 11-22-05  
INV. NO 2006060762

RECEIVED  
NOV 21 2005 Form CP-2/3  
KCC WICHITA