

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20835-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 14-4S-35W
990 feet from S Section Line, 330 feet from W Section Line
Lease Name: ROESCH A Well #: 1-14
County: RAWLINS Total Vertical Depth: 5043 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	291		

#163⁹⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/04/2005 1:35 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEITH VANPELT Company: MCCOY PETROLEUM CORPORATI Phone: (316) 636-2737

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 11/09/2005 5:45 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 4750' w/25 sxs.
2nd. Plug at 2830' w/25 sxs.
3rd. Plug at 2125' w/100 sxs.
4th. Plug at 340' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

District: 04

ND

Signed Ed Schumacher

(TECHNICIAN)

INVOICED
DATE 11-22-05
INV. NO. 2006060765

RECEIVED

NOV 21 2005

KCC WICHITA

Form CP-2/3

NOV 16 2005