

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21039-00-00
Spot: NESE Sec/Twnshp/Rge: 3-32S-33W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: CITIZENS STATE BANK Well #: 1-3
County: SEWARD Total Vertical Depth: 5965 feet

Operator License No.: 9953
Op Name: HARRIS OIL & GAS COMPANY
Address: 1125 17TH STREET, STE 2290
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5890	1750	WITH 200 SX CMT
SURF	8.625	1552		WITH 695 SX CMT <i>\$193⁸⁶</i>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2005 8:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: TOMMY THOMPSON Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: PUMP 2003 HULLS WITH 25 SX CMT. PLUG AT 1575' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2005 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

11/5/05: PUMP 100# HULLS WITH 35 SX CMT. TAG TOP OF CMT AT 5320'. 11/7/05: 1ST PLUG PULL TO 1580'. CIRCULATE HOLE & PUMP 50 SX CMT. 2ND PLUG DISPLACE WITH MUD. PULL TO 600'. CIRCULATE HOLE & PUMP 40 SX CMT. 3RD PLUG DISPLACE WITH MUD. PULL TO 40'. CIRCULATE HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5740	5746		

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE.

Plugged through: CSG

INVOICED
DATE 11-22-05
INV. NO 2006060776

District: 01



Signed

Jim Holland
PART II
(TECHNICIAN)

RECEIVED
NOV 22 2005
KCC WICHITA

FORM 2-23