

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21100-00-00  
Spot: E2SWSW Sec/Twnshp/Rge: 35-30S-33W  
660 feet from S Section Line, 4275 feet from E Section Line  
Lease Name: SIMPSON Well #: 5-35  
County: HASKELL Total Vertical Depth: 5619 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PARKWAY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5608	1800	WITH 200 SX CMT
SURF	8.625	1618		WITH 700 SX CMT #182

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/08/2005 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 5450' WITH 5 SX CMT. PLUG AT 3000' WITH 50 SX CMT. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/08/2005 4:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SAND OFF TO 5475' WITH 4 SX CMT ON TOP. 1ST PLUG PULL TO 1625'. PUMP 10 SX GEL & 50 SX CMT AT 1650'. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5527	5554		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

**INVOICED**  
DATE 11-22-05  
BY WILLIAM T78

District: 01



Signed

Jim Holland  
(TECHNICIAN)

**RECEIVED**  
NOV 22 2005  
KCC WICHITA

