

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21234-00-02
Spot: NESWNW Sec/Twnshp/Rge: 23-30S-34W
1650 feet from N Section Line, 990 feet from W Section Line
Lease Name: SCHNELLBACHER P C Well #: 3-523
County: HASKELL Total Vertical Depth: 5590 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PARKWAY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		3022		WITH 70 SX CMT
PROD	4.5	5589	2080	WITH 285 SX CMT <i>\$181</i>
SURF	8.625	1668		WITH 550 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/10/2005 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SANDED TO 4681' WITH 4 SX CMT. PLUG AT 1720' WITH 15 SX GEL & 50 SX CMT. PLUG AT 630' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2005 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SAND OFF TO 4680' WITH 4 SX CMT ON TOP. 1ST PLUG PULL TO 1720'. PUMP 15 SX GEL & 50 SX CMT. 2ND PLUG AT 630' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5354	5359		
5334	5336		
5252	5260		
4733	4738		


INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

DATE 11-22-05
INV. NO. 2006060978

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

RECEIVED
NOV 22 2005
KCC WICHITA

Form CP-2/3