

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21403-00-01
Spot: NWNW Sec/Twnshp/Rge: 24-29S-33W
660 feet from N Section Line, 625 feet from W Section Line
Lease Name: BRENNAN D Well #: 1-24
County: HASKELL Total Vertical Depth: 5750 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PARKWAY
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 5600 | | |
| DVT | | 2950 | | WITH 80 SX CMT |
| PROD | 4.5 | 5750 | 2320 | WITH 250 SX CMT |
| SURF | 8.625 | 1730 | | WITH 475 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2005 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 5080' WITH 4 SX CMT. PLUG AT 1760' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2005 12:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SAND OFF TO 5030' WITH 4 SX CMT ON TOP. 1ST PLUG PULL TO 1760'. PUMP 15 SX GEL & 50 SX CMT. 2ND PLUG AT 700' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


| Top | Bot | Thru | Comments |
|------|-----|------|----------|
| 2300 | | | |

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

INVOICED
DATE 11-22-05
INV. NO. 2006060778

District: 01



Signed

Jim Holland
(TECHNICIAN)

RECEIVED
NOV 22 2005
KCC WICHITA

Form CR 2/03