

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21533-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 24-15S-12W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HEINZE Well #: 7
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3348	0	200 SX CMT
SURF	8.625	212	0	150 SX CMT

#108⁸⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2005 12:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DAN A NIXON Company: NIXON, R.P. OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 800# hulls.
No squeezes found. Fluid level 450'. Deep casing leaks.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2005 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech shot a two hole shot at 1450' and 765'.
Express Well Service RIH with tubing to 1500'.
Allied rigged to tubing and pumped 175 sxs 60/40 pozmix with 800# hulls mixed in.
Pulled tubing to 1000'. Allied rigged to tubing and pumped 20 sxs 60/40 pozmix to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 20 sxs 60/40 pozmix.
Max. P.S.I. 250#. S.I.P. 100#.
Rigged to 8 5/8" casing and pumped 10 sxs 60/40 pozmix.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3310	3320		
3305	3310		
3296	3299		
3193	3196		
3167	3169		
3103	3105		
3088	3090		
3039	3041		
3012	3014		
2929	2932		
2868	2870		
2742	2744		
2732	2734		

Remarks: ALLIED CEMENTING COMPANY-TICKET #25653.

Plugged through: TBG

District: 04

Signed: [Signature]
(TECHNICIAN)

INVOICED
DATE 11-22-05
INV. NO. 2006060768

RECEIVED
NOV 21 2005
KCC WICHITA

NOV 16 2005

replacement card

R & H OIL & GAS CO
RUSSELL KS

24-15S-12W
NW SW SE

#7 HEINZE

site: 6 N & 3-1/2 E OF BEAVER KS
contr: BERGMAN DRILLING

co: RUSSELL
field: DRISCOLL

API 15-167-21533

well:
fr date 09/09/80 op date 12/27/80 drig comp 01/02/81 card issued 11/12/81 test revised 06/09/87

ELV: 1850 TOPO
 tops.....depth/datum
 RTD.....3350 -1500
 NO TOPS RPTD

IP status:
OIL, P 7 BOPD, ARB 3310-3320, 10/01/81
 INFO RELEASED: 6/9/87 - WAS OIL WELL - TEMP
 COMP
 CSG: 8-5/8" 212 / 150 SX, 4-1/2" 3348 / 200 SX
 NO CORES OR DSTS
 MICT - CO, PF (ARB) 3310-3320 (EST), AC'D, SO, POP,
 IPP 7 TO 8 BOPD, 10/1/81 - NO OTHER INFO RELEASED
 BY OPERATOR OR ON KCC RECORDS; ALL REQUESTS
 FOR INFO DENIED

COPYRIGHT 1997
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS