

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20371-00-00

Spot: W2SESE

Sec/Twnshp/Rge: 24-15S-12W

660 feet from S Section Line,

990 feet from E Section Line

Lease Name: HEINZE

Well #: 4

County: RUSSELL

Total Vertical Depth: 3331 feet

Operator License No.: 5252

Op Name: NIXON, R P OPERATIONS, INC

Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

CIBP		2650		
------	--	------	--	--

PROD	5.5	3323	0	UNKNOWN 100?
------	-----	------	---	--------------

SURF	8.625	313	0	200 SX CMT
------	-------	-----	---	------------

#108 26

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/14/2005 2:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: DAN A NIXON

Company: NIXON, R.P. OPERATIONS, INC.

Phone: (785) 628-3834

Proposed

Ordered 75 sxs 60/40 pozmix - 10% gel - 100# hulls.

Plugging

Lock set plug set at 2650' -test to 1000 lbs - stuck in hole before casing collapsed.

Method:

Holes in casing from 250' - 530'. Drilled out of casing at 522'.

04/27/1996 - Squeeze holes in casing from 250' - 530' with 200 sxs common with 300# shut in.

04/25/1996 - Pumped 80 sxs common down annulus 500# shut in.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/14/2005 4:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 510'.

Allied rigged to tubing and pumped 60 sxs cement with 100# hulls mixed in to circulate cement to surface.

Pulled tubing - rigged to 5 1/2" casing and pumped 10 sxs 60/40 pozmix.

Max. P.S.I. 500#. S.I.P. 500#.

Rigged to 8 5/8" casing - pressured to 400# immediately.

Perfs:

Top	Bot	Thru	Comments
3190	3196		
3170	3175		
3100	3104		
3085	3087		
3071	3073		
3035	3041		
2845	2847		
2839	2841		
2829	2831		
2819	2821		
2724	2728		

Remarks: ALLIED CEMENTING COMPANY-TICKET #25654.

Plugged through: TBG

District: 04

Signed

[Signature]

(TECHNICIAN)

INVOICED

DATE

11-22-05

CV. NO.

2006060768

RECEIVED

NOV 21 2005

KCC WICHITA

NOV 16 2005

RAY MADER
RUSSELL, KS.

#4 HEINZE

24-15-12W
APP W/2 SE SE

Contr. SHIELDS DRIG. COMPANY

Cty. RUSSELL

Geol. R. P. NIXON

Pool DRISCOLL

E. 1863 KB Cm. 10/23/69 Cp. 11/26/69 BP BHP 35 BOPD/ARB

API 15-167-20,371

LOG Tops	Depth	Datum
*ANH	753	+1110
TOP	2616	-753
HEEB	2904	-1041
TD	2922	-1059
BR LM	2993	-1130
LANS	3004	-1141
CONG	3272	-1409
ARB	3318	-1455
RID	3331	-1468

Csg. 8-5/8" 313/200 SX
5 1/2" 3323

DST 3035-95/1', 180' GIP, 305'

GSY OCM, BHP 1480-1320#/30"

FP 178-190#

DST 3165-3215/1', 10' V SL OIL SP

M, 18HP 90#/30", ALL OTHER

PRESS 0#

CO TO 3331 TD, 55 GALS ACID, FU

1800' OIL/2 HRS, 750 ACID, SWB LD,

NO TST, POP

NO CORES

*DRILLER'S TOP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS