

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20840-00-00
Spot: S2NE Sec/Twnshp/Rge: 27-16S-10W
1980 feet from N Section Line, 1320 feet from E Section Line
Lease Name: MONTGOMERY Well #: 1-A
County: ELLSWORTH Total Vertical Depth: 3359 feet

Operator License No.: 8653
Op Name: PETROLEUM TECHNOLOGIES, INC.
Address: 801 W. 47TH ST STE 412
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3354		125 SX CMT
SURF	8.625	368		225 SX CMT

4/109¹⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2005 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 11/04/2005 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3250' and capped with 5 sacks of cement. Cut off casing at 1702'. Pulled casing to 1400' and pumped 35 sacks of cement with 100 lbs of cotton hull. Pulled casing to 1000' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 418' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #22601

Perfs:

Top	Bot	Thru	Comments
3306	3312		
RECEIVED KCC DISTRICT #2 NOV - 8 2005 WICHITA, KS			

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 11-22-05
INV. NO 2006060769

RECEIVED
NOV 21 2005
KCC WICHITA