

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20177-00-01  
Spot: SWSE Sec/Twnshp/Rge: 26-28S-8W  
603 feet from S Section Line, 2154 feet from E Section Line  
Lease Name: SIMONS OWWO Well #: 1  
County: KINGMAN Total Vertical Depth: 4250 feet

Operator License No.: 5254  
Op Name: MIDCO EXPLORATION, INC.  
Address: 414 PLAZA DRIVE #204  
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4070		
PROD	4.5	4203		190 SX CMT
SURF	8.625	244		125 SX CMT

#138<sup>13</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/21/2005 8:00 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC  
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCO EXPLORATION, INC. Phone: (620) 786-9166

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/21/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

CIBP at 4070' with 25 sacks of cement on top of plug; 35 sacks of cement at 1250'; 35 sacks of cement at 750'; 130 sacks of cement at 300' to surface.

60/40 posmix with 4% gel  
Allied #20991

Perfs:

Top	Bot	Thru	Comments
4096	4100		

RECEIVED  
KCC DISTRICT #2  
OCT 31 2005  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
DATE 11.22.05  
INV. NO. 2006060766

RECEIVED  
NOV 21 2005  
KCC WICHITA

Form CP-2/3