

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02830-00-00
Spot: NWNWNWNE Sec/Twnshp/Rge: 4-9S-16W
5196 feet from S Section Line, 2429 feet from E Section Line
Lease Name: ADAMS D Well #: 6W
County: ROOKS Total Vertical Depth: 3380 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3379	0	w/175 sxs cmt
SURF	8.625	238	0	w/200 sxs cmt

\$10985

Well Type: EOR UIC Docket No: E03504.5 Date/Time to Plug: 11/09/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 250 sxs cement and 500# hulls.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2005 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

DV Tool at 1263' w/400 sxs cement.
Tied to 8 5/8" x 4 1/2" annulus - squeezed to 1000# P.S.I. - took no cement.
Tied to 4 1/2" casing - squeezed 225 sxs cement with 500# hulls.
Max. P.S.I. 300#. S.I.P. 300#.
Total of 225 sxs 60/40 pozmix - 10% gel and 500# hulls.

Remarks: ALLIED CEMENTING COMPANY. FLATLAND TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger A Moses
(TECHNICIAN)

INVOICED

DATE

11-22-05

INV. NO.

2006060771

RECEIVED

NOV 21 2005

KCC WICHITA

11-232 REPL. COMP.

MAP NO. REELS
Kans. COUNTY Rooks
Cities Service Oil Co., Russell, Kansas
#6-W ARM Adams
Laton
Murfin Drlg. Tools

SEC 4-9S-16W
LOC App NW NW NE
386 FT/FR West
50 FT/FR North
1980 OF 1982
of NE/4

COG
INT

FR. 10/14/63 SPUD 10/16/63 COMP. 11/26/63
TO 3380 FM. BKc P3TD 3353

PRODUCING FM. FROM TO PERFORMING W/OLES TREATMENT

Completion Record
Casing Record

SWDW in Lansing

8" @ 238 w/200 sx.
4 1/2" @ 3379 w/175 sx.

Data Inc.

KB Spl Tops:

Anh	1233	+ 749
B/Anh	1275	+ 707
Hb	3046	
Tor	3065	
Lans	3084	
BKc	3342	
RTD	3380	

KB Log Tops:

Hb	3043	-1052
Tor	3062	-1080
Lans	3083	-1101
BKc	3341	-1359
LTD	3355	-1373

RTD 3380, 4 1/2" @ 3379 w/175 sx., DV Tool @ 1263' w/400 sx.,
CO 3353, P3TD, GRN Log 2500-3353, Pf 3333, 3305, 3273, 3253, 3331,
3207, 3187, 3176, 3166, 3151, 3139, 3125, 3107, 3095, w/total
14/shots, 9100A (Reg) Acid survey log, shows chann. "A" through
"G" zones, Reperf 24/3279-67, 18/3256-47, 20/3235-25, 14/3211-04
16/3192-84, 6/3177-74, 8/3168-64, 10/3154-49, 8/3141-37,
12/3128-22, 8/3109-05, 8/3098-94 (Total 166 shots) Set 2" cem.
lined tbg w/baker pkr @ 3061, no input tests, Completed as SWDW
in Lans

COMPLETE (11/16/63)

REPLACEMENT COMPLETION: (12/3/63)

To correct spot
Was - 50' So. of C of No. Line
Is - App NW NW NE