

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20316-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 16-14S-10W
2202 feet from S Section Line, 3126 feet from E Section Line
Lease Name: BAKER Well #: 5
County: ELLSWORTH Total Vertical Depth: 2952 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2951		100 SX CMT
SURF	8.625	263		165 SX CMT

95 94

Well Type: EOR UIC Docket No: E16708.3 Date/Time to Plug: 09/20/2005 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 626-3596

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 09/28/2005 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 50' above perforations and capped with 5 sacks of cement. Perforated pipe at 1250', 900', and 315'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 315' and pumped 47 sacks of cement and circulated from 315' to surface.

60/40 posmix with 4% gel

Allied Cementing #21016

Perfs:

Top	Bot	Thru	Comments
2862	2877		

RECEIVED
KCC DISTRICT #2
OCT 3 1 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

INVOICED
DATE 11-22-05
INV. NO. 2006060773

RECEIVED
NOV 21 2005
KCC WICHITA
Form CP-2/3