

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-19351-00-01

Spot: NWSW

Sec/Twnshp/Rge: 3-25S-17E

1960 feet from S Section Line, 4302 feet from E Section Line

Lease Name: PIQUA

Well #: 0-2

County: WOODSON

Total Vertical Depth: 922 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

Address: 4700 HIGHWAY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	916		30 SX CMT
SURF	10	11		

\$35⁰⁰

Well Type: GS

UIC Docket No:

Date/Time to Plug: 11/14/2005 10:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING & ROUST SVS, INC.

Proposal Rcvd. from: BERNIE ROCKERS

Company: SOUTHERN STAR CENTRAL PIPEL Phone: (785) 448-4816

Proposed Plugging Method: RUN 1" TUBING DOWN BACK SIDE OF 2" PIPE AND WASH DOWN TO BOTTOM. RUN SEPARATE STRING OF 1" INSIDE OF 2" TO BOTTOM OF HOLE AND FILL WITH CEMENT FROM BOTTOM UP. ONCE HOLE IS FULL TIE ONTO 2" AND SQUEEZE CEMENT WITH SOME PRESSURE. THEN FILL BACK SIDE OF 2" FROM BOTTOM TO TOP UNTIL CEMENT SHOWS AT SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: PARTIAL

Date/Time Plugging Completed: 11/15/2005 6:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE 2" CASING TO 916'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 10" ANNULUS TO 660'. THE ANNULUS WAS WASHED. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

NOV 16 2005 CPT

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED

NOV 21 2005

KCC WICHITA

INVOICED

DATE

11.22.05

INV. NO

2006060772