

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

KCC WICHITA

Lease Operator: MIDCO Exploration, Inc.

Address: 414 Plaza Drive, Suite 204

Phone: (630) 655-2198 Operator License #: 5254

Type of Well: D&A Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: October 20, 2005 (Date)

by: (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. (repeated three times)

API Number: 15-095-21984-0000

Lease Name: Ramsey

Well Number: 3

Spot Location (QQQQ): SE - SW - NW - KCC BEN 2210-3093 Feet from North / South Section Line

010-4660 Feet from East / West Section Line

Sec. 35 Twp. 28 S. R. 8 East West

County: Kingman

Date Well Completed: 10/20/2005

Plugging Commenced: 10/21/2005

Plugging Completed: 10/21/2005

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes data for Surface and Production casing.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set cast iron bridge plug at 4090'. Dump 2 sacks cement; cut casing at 2548'; pump in 35 sacks at 1250'; 35 sacks at 750'; 100 sacks at 300; top off with 10 sacks

Name of Plugging Contractor: Leiker Well Service License #: 30891

Address: 2710 Jackson Great Bend, KS 67530

Name of Party Responsible for Plugging Fees: MIDCO Exploration, Inc.

State of Illinois County, DuPage, ss.

Earl J. Joyce, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) 414 Plaza Drive, Suite 204 Westmont, IL 60559

SUBSCRIBED and SWORN TO before me this 17th day of November 20 05

Nancy L. Macynas Notary Public

My Commission Expires: OFFICIAL SEAL Nancy L. Macynas Notary Public, State of Illinois My Commission Exp. 06/24/2006

Handwritten initials 'BM'

# ALLIED CEMENTING CO., INC. 20922

Federal Tax I.D.# ~~00000000~~

TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Medicine L.P.G.Ks.

DATE <u>9-26-05</u>	SEC. <u>35</u>	TWP. <u>28S</u>	RANGE <u>8W</u>	CALLED OUT <u>1:00 P.M.</u>	ON LOCATION <u>3:30 P.M.</u>	JOB START <u>6:30 P.M.</u>	JOB FINISH <u>7:20 P.M.</u>	
LEASE <u>Ramsey</u>		WELL # <u>#3</u>		LOCATION <u>Spivey Ball Park RD</u>		COUNTY <u>Kingman</u>	STATE <u>Ks</u>	
OLD OR <u>NEW</u> (Circle one)			N, TO STOP sign 1/4 N E into					

CONTRACTOR Duke #2

TYPE OF JOB long string

HOLE SIZE 7 7/8 T.D. 4400

CASING SIZE 4 1/2 DEPTH 4244.97

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE 4 1/2 DEPTH 4400

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 1000 PSI MINIMUM 100 PSI

MEAS. LINE \_\_\_\_\_ SHOE JOINT 39.65

CEMENT LEFT IN CSG. 39.65 FT

PERFS. \_\_\_\_\_

DISPLACEMENT Kcl/water 6 7/8 BBLS

EQUIPMENT

PUMP TRUCK CEMENTER David W.

# 397 HELPER CHRIS R.

BULK TRUCK \_\_\_\_\_

# 353 DRIVER Greg K.

BULK TRUCK \_\_\_\_\_

# \_\_\_\_\_ DRIVER \_\_\_\_\_

OWNER Midco Exploration

CEMENT

AMOUNT ORDERED 190sx ASC + 5# Kol-seal

+ 7% Gas Block 25sx 60' 40' 4.500gal

Mud clean C 500gal ASF 7gal KCl

COMMON	<u>15</u>	<u>A</u>	@	<u>8.70</u>	<u>130.50</u>
POZMIX	<u>10</u>		@	<u>4.70</u>	<u>47.00</u>
GEL	<u>1</u>		@	<u>14.00</u>	<u>14.00</u>
CHLORIDE			@		
ASC	<u>190</u>		@	<u>10.75</u>	<u>2042.50</u>
<u>Kol Seal</u>	<u>950#</u>		@	<u>.60</u>	<u>570.00</u>
<u>Gas Block</u>	<u>7#</u>		@	<u>7.40</u>	<u>51.80</u>
<u>Mud Clean C</u>	<u>500 gal</u>		@	<u>1.25</u>	<u>625.00</u>
<u>ASF</u>	<u>500 gal</u>		@	<u>1.00</u>	<u>500.00</u>
<u>Clas Pro</u>	<u>7 gal</u>		@	<u>22.90</u>	<u>160.30</u>
			@		
			@		
HANDLING	<u>269</u>		@	<u>1.60</u>	<u>430.40</u>
MILEAGE	<u>50 x 269 x .06</u>				<u>807.00</u>
TOTAL					<u>5378.50</u>

**REMARKS:**

Pipe on bottom Break fire Pump  
3 Water 12 BBLS, ASF 12 BBLS, Mud  
Clean "C" 3 BBLS, water Plug Rat + Mouse  
Pump 190sx ASC + 5# Kol-seal + 7%  
Gas Block. Shut Down Wash Pump  
lines, Displace w/ Kcl/water 6 low  
Rat + Mouse Plug Float did Hold  
Wash up Rig Down.

CHARGE TO: Midco Exploration

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB	<u>4244</u>		
PUMP TRUCK CHARGE			<u>1370.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>50</u>	@	<u>5.00 250.00</u>
MANIPULATOR RENT		@	<u>75.00 75.00</u>
		@	
		@	
TOTAL			<u>1695.00</u>

**RECEIVED**  
**NOV 21 2005**

**KCC WICHITA**

**PLUG & FLOAT EQUIPMENT**

<u>4 1/2</u>			
<u>1-Guide Shoe</u>	@	<u>125.00</u>	<u>125.00</u>
<u>1-AFU Insert</u>	@	<u>210.00</u>	<u>210.00</u>
<u>5-Centralizers</u>	@	<u>45.00</u>	<u>225.00</u>
<u>5-Top BBLS</u>	@	<u>55.00</u>	<u>275.00</u>
<u>1-Rubber Plug</u>	@	<u>48.00</u>	<u>48.00</u>
TOTAL			<u>883.00</u>

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

**ANY APPLICABLE TAX  
WILL BE CHARGED  
UPON INVOICING**

SIGNATURE x David H Mayfield

TAX \_\_\_\_\_

TOTAL CHARGE 7956.50

DISCOUNT 795.65 IF PAID IN 30 DAYS

SIGNATURE x David H Mayfield

PRINTED NAME