

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. 2-5-1-17
RECEIVED
NOV 18 2005

API NUMBER 15-167-23311-0000

LEASE NAME Heffel

WELL NUMBER 1

1,150 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 16 TWP. 13 RGE. 12 ~~NE~~ or (W)

COUNTY Russell

Date Well Completed 11-9-05

Plugging Commenced 11-9-05

Plugging Completed 11-9-05

KCC WICHITA
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Brungardt Oil & Leasing, Inc.

ADDRESS PO Box 871, Russell, KS 67665

PHONE (785) 483-4975 OPERATORS LICENSE NO. 3956

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-8-05 (date)

by Jay Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,210'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	347'	Cmtd. w/225 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Push bridge plug to 3,149', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 585', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 325', pump 100 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address SHIELDS BLDG., RUSSELL, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BRUNGARDT OIL & LEASING, INC.


STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor
(Employee of ~~OPERATOR~~) or ~~CONTRACTOR~~
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 15th day of November, 2005

My Commission Expires:  5-26-07
Keith Phillips Notary Public



Shields

WELL LOG

RECEIVED

NOV 18 2005

Russell, Kansas

KCC WICHITA

Operator: Brungardt Oil & Leasing, Inc.


Well: Heffel #1

Commenced: November 2, 2005

Completed: November 9, 2005

Contractor: Shields Drilling Co.

Well Description: 1,150' FSL, 330' FEL
SW/4 Sec.16-13S-12W
Russell Co., KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	347'	Cmtd. w/225 sax

Elevation: 1,634' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Surface clay, sand, shale	200'	
Shale and sandstone	350'	
Redbed	563'	
Anhydrite	602'	
Redbed and shale	915'	
Shale	2,725'	
Lime	3,160'	
Dolomite	3,210'	RTD

Notes