

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

NOV 21 2005

KCC WICHITA

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: MIDCO Exploration, Inc.

Address: 414 Plaza Drive, Suite 204

Phone: (630) 655-2198 Operator License #: 5254

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: October 20, 2005 (Date)

by: (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Mississippi Depth to Top: 4094 Bottom: 4100 T.D. 4250

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15 - 095-20177-0001

Lease Name: Simons OWWO

Well Number: 1

Spot Location (QQQQ): Approx - 90' W - SW - SE 660 603 Feet from North / South Section Line

2070 2154 Feet from East / West Section Line

Sec. 26 Twp. 28 S. R. 8 East West

County: Kingman

Date Well Completed: 2/5/2003

Plugging Commenced: 10/20/2005

Plugging Completed: 10/20/2005

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes data for Surface casing from 244' to 4203'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set cast iron bridge plug at 4070'; pump 25 sacks of cement. Cut casing at 3230'; pump 35 sacks at 1250'; pump 35 sacks at 700'; 100 sacks at 300'; had cement to surface.

Name of Plugging Contractor: Plains, LLC License #: 33645

Address: P.O. Box 346 Ness City, KS 67560

Name of Party Responsible for Plugging Fees: MIDCO Exploration, Inc.

State of Illinois County, DuPage, ss.

Earl J. Joyce, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 414 Plaza Drive, Suite 204 Westmont, IL 60559

SUBSCRIBED and SWORN TO before me this 17th day of November 20 05

Nancy L. Macynas Notary Public My Commission Expires:



Handwritten initials 'Bm' at the bottom right.

ALLIED CEMENTING CO., INC.

20991

Federal Tax I.D.# ~~61-22348~~

P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge, KS

DATE <i>21 Oct 05</i>	SEC. <i>26</i>	TWP. <i>28</i>	RANGE <i>B</i>	CALLED OUT <i>0830 AM</i>	ON LOCATION <i>1000 AM</i>	JOB START	JOB FINISH
LEASE # <i>Simon #</i>	WELL # <i>1</i>	LOCATION <i>Spivey, KS N to Ramsay's corner</i>			COUNTY <i>Kingman</i>	STATE <i>KS</i>	
OLD OR NEW (Circle one)		<i>1/2 E, N/into</i>					

CONTRACTOR *Plains inc.*

TYPE OF JOB *old hole Plug*

HOLE SIZE *7 7/8* T.D.

CASING SIZE *4 1/2* DEPTH

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT *Fresh H₂O*

EQUIPMENT

PUMP TRUCK CEMENTER *D. Felio*

352 HELPER *Chas R.*

BULK TRUCK

356 DRIVER *Greg K.*

BULK TRUCK

DRIVER

OWNER *Midco Exploration*

CEMENT

AMOUNT ORDERED *200 sx 60:40:4*

<used 200 sx>

COMMON	<i>120</i>	<i>A</i>	@	<i>8.70</i>	<i>1044.00</i>
POZMIX	<i>80</i>		@	<i>4.70</i>	<i>376.00</i>
GEL	<i>7</i>		@	<i>14.00</i>	<i>98.00</i>
CHLORIDE			@		
ASC			@		
RECEIVED					
<i>NOV 21 2005</i>					
KCC WICHITA					
HANDLING	<i>207</i>		@	<i>1.60</i>	<i>331.20</i>
MILEAGE	<i>35</i>	<i>x 207</i>	<i>x</i>	<i>.06</i>	<i>434.70</i>
					TOTAL <i>2283.90</i>

REMARKS:

Load hole with 20 Bbls Fresh, Pump 35 sx cement, Disp. with 14 1/2 Bbls, Pull up to 750'

Pump 35 sx cement, Disp. with 7 1/2 Bbls Fresh H₂O, Pull up to 300' pump 130 sx cement to surface.

SERVICE

DEPTH OF JOB *1250'*

PUMP TRUCK CHARGE *600.00*

EXTRA FOOTAGE @

MILEAGE *35* @ *5.00* *175.00*

MANIFOLD @

TOTAL *775.00*

CHARGE TO: *Midco Exploration*

STREET

CITY STATE ZIP

PLUG & FLOAT EQUIPMENT

@

@

@

@

@

TOTAL

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the invoice.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

TAX

TOTAL CHARGE ~~2283.90~~

DISCOUNT ~~2283.90~~ IF PAID IN 30 DAYS

SIGNATURE *David H Mayfield*

David H Mayfield
PRINTED NAME