

RECEIVED

NOV 23 2005

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD KCC WICHITA

K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9/23/05 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) 3978-83, 4002-06, 3959-63, Depth to Top: Bottom: T.D. 3939-43, 3888-92, 3848-50, Depth to Top: Bottom: T.D. 3840-44, 3810-14, 3898-3904 Depth to Top: Bottom: T.D.

API Number: 15 - 065-20324-00-00

Lease Name: SE Gano Unit

Well Number: #4-2

Spot Location (QQQQ): SE - SW - NE - 2970 Feet from North South Section Line

1650 Feet from East West Section Line

Sec. 12 Twp. 10 S. R. 24 East West

County: Graham

Date Well Completed: 5/70

Plugging Commenced: 10/2805

Plugging Completed: 10/28/05

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Surface and Production data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig Up Allied Cementing: Pumped 75 sx 60/40 Poz, 10% gel, 300# hulls. Pulled tbg to 1560'. Pumped 125 sx 60/40 Poz, 10% gel to circ cement to surface. TOH w/tbg. Tied onto 4 1/2" csg. Pumped 50 sx 60/40 Poz, mas pressure 500#, ISIP 400#. Tied onto 8 5/8" surface pipe. Pumped 50 sx 60/40 Poz, 100# hulls, 200# max pressure, 100# ISIP. Plugged at 11:30 am. Witnessed by Rogert Moses with KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.


State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 22nd day of November, 2005

Susan Brady My Commission Expires: 11-4-07 Notary Public

[Handwritten mark]