

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-185-23332-0000
LEASE NAME Leo
WELL NUMBER 1-26

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1200 Ft. from North Line of Section
330 Ft. from West Line of Section

KCC
BEM
11-23-05
11-23
11-23

LEASE OPERATOR Mull Drilling
ADDRESS P.O. Box 2758
CITY, STATE, ZIP Wichita, Kansas 67201-2758
PHONE # 316-264-6366
Character of Well Dry and Abandoned

SPOT LOCATION S2-NW-NW S2-SW-NW-NW
Section 26 Township 21s Range 13w
County Stafford
Date Well Completed 04/01/05
Date Plugging Commenced 04/01/05 11-17-05
Date Plugging Completed 04/01/05 11-17-05

The plugging proposal was approved on November 17, 2005 (date)
by Mike Maier (KCC District Agent's Name)

Is ACO-1 Filed? _____ If not, is well log attached? _____ Yes
Producing Formation(s) D&A Depth to Top _____ Bottom _____ T.D. 3800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	240			
Redbeds	Shale	240	280	8-5/8"	265	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugging orders from Mike Maier on 11/17/05. Plugged with 175 sks 64/40 Poz, 6% Gel & 1/4# Flo-seal. Heavy mud in hole and between all plugs. Bottom plug at 3473' - 50 sks, 2nd plug at 750' - 40 sks, 3rd plug at 290' - 50 sks and top plug at 60' - 20 sks. Rathole - 15 sks, no mousehole. Job completed at 4:30 pm on 11/17/05.
Allied Cementing ticket # 22595. Sterling reported plugging to KCC 11/18/05.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary Talbott (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M Talbott

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 21 day of November, 2005



Karissa Schelling
(Notary Public)

RECEIVED
NOV 22 2005
KCC WICHITA

My Commission Expires: _____

Form CP-4
Revised 12-92

BEM

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Leo 1-26

LOCATION: S/2 NW NW
API: 15-185-23332-0000

Section 26 T 21s R 13w
Stafford County, Kansas

OWNER: Mull Drilling
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 08-Nov-05
COMPLETED: 17-Nov-05

TOTAL DEPTH: DRILLER 3800 FEET
LOGGER 3798 FEET

Ground Elevation: 1870
KB Elevation: 1879

LOG

0 -	2 FEET	Top Soil	From Water Well Driller
2 -	18 FEET	Clay	
18 -	25 FEET	Fine Sand	
25 -	50 FEET	Clay	
50 -	75 FEET	Fine Sand	
75 -	100 FEET	Sand and Gravel	
100 -	715 FEET	Redbeds	
715 -	735 FEET	Anhydrite (Driller's)	
735 -	1550 FEET	Shales and Salt	
1550 -	3650 FEET	Limestone, Shale and Dolomite	
3650 -	3800 FEET	Arbuckle	

CASING RECORDS

Surface Casing-8-5/8"

Spud at 1:45 pm on 11/08/05. Drilled 12-1/4" hole to 280'. Ran 6 joints of new, 20#, 8-5/8" surface casing, tallied 265.17', set at 280' KB. Cemented with 275 sx 70/30 Poz, 2% Gel, 3% CC. Cement did circulate. Plug down at 8:00 am on 11/08/05. Allied Cementing ticket # 22591. Welder strapped bottom 3 joints together and welded collars on remaining joints.

Production Casing

Plugging orders from Mike Maier on 11/17/05. Plugged with 175 sks 64/40 Poz, 6% Gel & 1/4# Flo-seal. Heavy in hole and between all plugs. Bottom plug at 3473' - 50 sks, 2nd plug at 750' - 40 sks, 3rd plug at 290' - 50 sks and top plug at 60' - 20 sks. Rathole - 15 sks, no mousehole. Job completed at 4:30 pm on 11/17/05. Allied Cementing ticket # 22595. Sterling reported plugging to KCC 11/18/05.

DEVIATION SURVEYS

3/4 degree(s) at 280 feet
1 degree(s) at 3325 feet
1-1/2 degree(s) at 3569 feet

RECEIVED
NOV 22 2005
KCC WICHITA