

15-163-00831-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

ROOKS County, Sec. 15 Twp. 7S Rge. 20 (E) W (W)

Location as "NE/CNW&SW" or footage from lines NW NW NW

Lease Owner EMPIRE DRILLING COMPANY AND D. L. SOMERS

Lease Name SAMMONS Well No. 1

Office Address 407 BROWN BUILDING, WICHITA 2, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 8-31 19 55

Application for plugging filed 8-31 19 55

Application for plugging approved 8-31 19 55


Plugging commenced 8-31 19 55

Plugging completed 8-31 19 55

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well ELDON PETTY

Producing formation Depth to top Bottom Total Depth of Well 3539 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE		0	161'	8 5/8"	161'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

BOTTOM PLUG @ 325' WITH 1/2 SACK HULLS AND 15 SACKS OF CEMENT.

TOP PLUG @ 40' WITH 1/2 SACK HULLS AND 10 SACKS OF CEMENT.



9-9-55

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY

Address 407 BROWN BUILDING, WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, DAN J. KORNFELD (Employee of owner) or (owner) or operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) DAN J. KORNFELD

407 BROWN BUILDING, WICHITA 2, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 7TH day of SEPTEMBER, 19 55

[Signature] Notary Public.

My commission expires DECEMBER 10, 1956

PLUGGING
FILE SEC 15 T 7 R 200
BOOK PAGE 146 LINE 40

15-163-00831-00-00

L O G

COMPANY: EMPIRE DRILLING COMPANY AND D. L. SOMERS

CONTRACTOR: EMPIRE DRILLING COMPANY

FARM: SAMMONS NO. 1

LOCATION: NW NW NW, SEC. 15-7S-20W
ROOKS COUNTY, KANSAS

COMMENCED: 8-23-55

COMPLETED: 8-31-55

0	TO	192	SURFACE
192	TO	1150	SHALE AND SHELLS
1150	TO	1360	SAND AND SHALE
1360	TO	1622	SHALE AND SHELLS
1622	TO	1655	ANHYDRITE
1655	TO	2520	SHALE AND SHELLS
2520	TO	2630	SHALE AND LIME
2630	TO	3045	SHALE AND SHELLS
3045	TO	3275	LIME AND SHALE
3275	TO	3539	LIME
3539			R.T.D.

SET 8 5/8" SURFACE CASING AT 161' WITH 115 SACKS OF CEMENT.

ELEVATION: 2058 K.B.

TOPS: ANHYDRITE 1622'; HEEBNER 3244'; TORONTO 3266'; LANSING-KANSAS CITY 3282';
BASE KANSAS CITY 3482'; BASAL PENNSYLVANIAN CONGLOMERATE 3526'; ARBUCKLE
3530'; R.T.D. 3539'.

D.S.T. #1 3424' TO 3446'; D.S.T. #2 3446' TO 3455'; D.S.T. 3524' TO 3539'.

D & A

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE SAMMONS #1, NW NW NW, SECTION 15, TOWNSHIP 7 SOUTH, RANGE 20 WEST, ROOKS COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.


 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 7TH DAY OF SEPTEMBER, 1955.

MY COMMISSION EXPIRES DECEMBER 10, 1956


 NOTARY PUBLIC

PLUGGING
 FILE SEC-15-T7-R20W
 BOOK PAGE 146 LINE 40

RECEIVED
 DEPARTMENT OF REVENUE
 SEP 9 1955