

RECEIVED

NOV 21 2005

Form CP-4

December 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: R.P. Nixon Oper., Inc.

Address: 207 West 12th St. Hays, KS 67601

Phone: (785) 628-3834 Operator License #: 5252

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11.1.05 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

see attached

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-21,533-00-00

Lease Name: Heinze

Well Number: 7

Spot Location (QQQQ): NW - SW - SE -

990 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 24 Twp. 15 S. R. 21 12 East West

County: Russell

Date Well Completed: Jan. 1981

Plugging Commenced: 11.14.05

Plugging Completed: 11.14.05

KCC
BEM
11-23-05
TYPE 0

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	212'	none
				4 1/2"	3348'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated at 1450' and 765' - 2/spf. Ran tubing to 1500' and pumped 175 sx of 60/40 Pozmix, 10% gel and cement circulated intermittently. Pulled tubing to 1000' and pumped 20 sx of same cement and cement circulated. Pulled all tubing from well and pumped down casing with 22 sx of same cement with 250# pressure with an ISIP of 100#. Used 800# of hulls total. Tied on to 4 1/2" annulus and pumped 2 sx of same cement at 500# pressure and a shut-in pressure of 300#. Pat Staab on location.

Name of Plugging Contractor: Express Well Service & Supply License #: 6426


Address: Box 19 Victoria, KS 67671-0019

Name of Party Responsible for Plugging Fees: R.P. Nixon Oper., Inc.

State of Kansas County, Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) 207 West 12th Street Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 18th day of November, 20 05

[Handwritten Signature] My Commission Expires: 3-12-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Signature]

RECEIVED
NOV 21 2005
KCC WICHITA

CP-4 attachment

#7 Heinze producing intervals

3310'-20'	3305'-10'	3296'-99'	3193'-96'	3167'-69'
3103'-05'	3088'-90'	3039'-41'	3012'-14'	2929'-32'
2868'-70'	2742'-44'	2732'-34'		

BERGMAN DRILLING, INC.

DRILLERS LOG


RECEIVED
NOV 21 2005
KCC WICHITA

Re: Heinze# 7
NE SW SE Section 24-15S-12W
Russell County, Kansas


OPERATOR: R & H Oil & Gas Company
CONTRACTOR: Bergman Drilling, Inc.
COMMENCED: December 27, 1980
COMPLETED: January 4, 1981
TOTAL DEPTH: 3350' Set 212' 8 5/8" w/150 sacks


0	215	Post Rock
215	638	Shale & Red Bed
638	920	Red Bed & Shale
920	1475	Shale
1475	1760	Lime & Shale
1760	1915	Shale & Lime
1915	1995	Shale
1995	2425	Lime & Shale
2425	2665	Shale & Lime
2665	2777	Shale
2777	2895	Lime & Shale
2895	3025	Lime & Shale
3025	3110	Shale
3110	3167	Lime & Shale
3167	3209	Lime & Shale
3209	3280	Lime
3280	3345	Lime & Sand w/ Delomite
3345	3350	Sand & Lime
3350		RTD Set 4 1/2" @ 3348 1/2 w/200 sx.

We certify that the above and foregoing to be true and correct copy of the drillers log on the # 7 Heinze, located in Russell County, Kansas as revealed by the records of Bergman Drilling, Inc.


Harold I. Bergman

Subscribed and sworn to before me this 5th day of January, 1981.


Alma A. Neises, Notary Public
My commission expires May 31, 1982



ALLIED CEMENTING CO., INC. 25653

Federal Tax I.D.# XXXXXXXXXX

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>11/14/05</u>	SEC <u>24</u>	TWP. <u>15S</u>	RANGE <u>12W</u>	CALLED OUT <u>10:00 am</u>	ON LOCATION <u>11:30 am</u>	JOB START <u>12:00 pm</u>	JOB FINISH <u>2:00 pm</u>
LEASE <u>Hoover</u>	WELL # <u>7</u>	LOCATION <u>Occurrence + 1-70</u>		<u>55</u>	COUNTY <u>Russell</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)		<u>12W 55 E into</u>					

CONTRACTOR Express Well Service

TYPE OF JOB Old Hole Plug

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 DEPTH 3350

TUBING SIZE 2 3/4 DEPTH 1500

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 500 psi MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED 250 @ 1.561

800 # Halls

COMMON @ _____

POZMIX @ _____

GEL @ _____

CHLORIDE @ _____

ASC @ _____

HANDLING @ _____

MILEAGE @ _____

RECEIVED
NOV 21 2005
KCC WICHITA

EQUIPMENT

PUMP TRUCK CEMENTER Shane

366 HELPER Fred

BULK TRUCK _____

396 DRIVER Gary

BULK TRUCK _____

_____ DRIVER _____

REMARKS:

1500 Cmc Cement with 195 sh
800 halls Put 10 shs down back in
20 shs down casing 250 psi
Package shot in @ 500 psi

TOTAL _____

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____

EXTRA FOOTAGE @ _____

MILEAGE @ _____

MANIFOLD @ _____

TOTAL _____

PLUG & FLOAT EQUIPMENT

@ _____

@ _____

@ _____

@ _____

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

Thanks
[Signature]

SIGNATURE _____

PRINTED NAME _____