

API NUMBER 163-22,935  
 LEASE NAME BELLERIVE 00-00

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER A#1  
1650 Ft. from S Section Line  
2310 Ft. from E Section Line

LEASE OPERATOR ERIC WADDELL  
 ADDRESS Box 349 NATOMA KS 67651  
 PHONE#(913) 885-4497 OPERATORS LICENSE NO. 6725

SEC. 21 TWP. 7 RGE. 20 (E) or (W)  
 COUNTY ROOKS

Character of Well D&A,  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 7/19/87  
 Plugging Commenced 8/25/87  
 Plugging Completed 8/28/87

Did you notify the KCC District Office prior to plugging this well? yes (Dale Baltazar)  
 Which KCC Office did you notify? HAYS KS

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC "G"	WATER	3360	62	4 1/2" 10#	3522'	2500'
LKC "J, K, L"	WATER	3442	74	8 5/8" 20#	372'	NONE
LKC A	WATER	3280	84			
TORONTO	WATER	3362	68			
ARBuckle	WATER	3525	TD			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand plug 3425 to TD (ARBuckle) w/ 4 sks cement on Top, w/ dump bailer  
10sks Rathole  
290 sks 65/35 Poz, 10% gel, 2% ecmanite, w/ 500# cottonseed hulls w/ pump truck @  
well head Max Press. 400# Final Pressure 100# Supervised by Dale Baltazar (KCC)  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING, INC License No. \_\_\_\_\_  
 Address P.O. Box 31 RUSSELL, KS 67665  
 STATE OF KANSAS COUNTY OF Osborne, SS.

Tracy L. Cooley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tracy L. Cooley  
 (Address) Box 349, NATOMA KS 67651

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 87

My Commission Expires: 3-28-88

Reva F. Musgrove  
 Notary Public COMMISSION



SEP 17 1987  
 9-17-87  
 CONSERVATION DIVISION  
 Wichita, Kansas