


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks County. Sec. 9 Twp. 7 Rge. 20 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C SW SW  
Lease Owner Shields Oil Producers, Inc.  
Lease Name Le Sage Well No. 1  
Office Address Shields Bldg., Russell, Kansas 67665  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 6-27 19 74  
Application for plugging filed 6-27 19 74  
Application for plugging approved 6-27 19 74  
Plugging commenced 6-27 19 74  
Plugging completed 6-27 19 74  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3,750 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	204'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole w/heavy mud  
Push bridge plug to 720'  
Spotted 70 sax cement on plug thru 4 1/2" drill pipe  
Fill hole w/heavy mud  
Push bridge plug to 185'  
Spotted 20 sax cement on plug thru 4 1/2" drill pipe  
Push bridge plug to 40' w/1/2 sax hulls on plug  
Dump 10 sax cement on plug to cellar

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1974

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Shields Drilling Co., Inc.  
Address Shields Bldg., Russell, Kansas 67665

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
R. L. Shields (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Shields  
Shields Bldg., Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 19 74

My commission expires May 26, 1975  
Rush Phillips  
Notary Public.



15-163-20528-00-00


Shields

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers, Inc.  
 Well: LeSage #1  
 Commenced: June 18, 1974  
 Completed: June 27, 1974  
 Contractor: Shields Drilling Co., Inc.

Well Description: C SW SW  
 Sec. 9-7S-20W  
 Rooks Co., Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	204'	Cmtd. w/140 sax

Elevation: 2,192' RB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

Top soil, clay & sand	140'
Shale	210'
Shale & shells	950'
Sand	1,000'
Shale	1,250'
Sand	1,360'
Shale	1,745'
Anhydrite	1,774'
Shale & shells	1,960'
Shale & lime	3,160'
Lime	3,750' RTD

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 8 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas  
 County of Russell

I certify that to the best of my knowledge this is a true and accurate copy of the drillers log of the LeSage #1 located C SW SW, Section 9-7S-20W, Rooks County, Kansas.

Richard L. Shields  
 Richard L. Shields, President

Notary Public Lush Phillips

My commission expires May 26, 1975