

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-22,624-00-00

LEASE NAME Roy

WELL NUMBER 1.

SPOT LOCATION SW SW SW

SEC. 8 TWP. 7S RGE. 20W(E) or (W)

COUNTY Rooks

Date Well Completed 2-8-85

Plugging Commenced 2-8-85

Plugging Completed 2-8-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Frontier Oil Company

ADDRESS 125 N. Market, Ste 1720,

PHONE # (316) 263-1201 OPERATORS LICENSE NO. 5140

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? David Wann, Hays.

Is ACO-1 filed? Yes If not, is well log attached? Not logged.

Producing formation N/A Depth to top \_\_\_\_\_ bottom T.D. 3625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Hard Sand, Sand & Shale	170 sx 60-40 Poz 2% gel 3% cc.	-0-	215'	8-5/8"	208'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged at 3590'/20sx, 1700'/20sx, 1020'/100sx 1 sk floseal, 250'/40sx, 40'/10sx brdg. plug 1 sk hulls. Rathole/10sx. Cemented with 200sx 50-50 poz 6% gel 3% cc. (Plugs calculated by displacement).

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. N/A

Address P O Box 31, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Sedgwick, ss. STATE CORPORATION COMMISSION

Jean Angle (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jean Angle

(Address) 125 N. Market, Wichita, Ks.

02-25-1985  
FEB 25 1985  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1985

Stella Sewell  
Notary Public

