

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22527-00-01
Spot: NENENE Sec/Twnshp/Rge: 9-7S-20W
4950 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: ROY Well Number: 6-1
County: ROOKS Total Vertical Depth: 3650 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 328 225 SX \$118.63
Production: Size 4.5 feet: 3612 200 DV @ 1709 350 SX
Liner: Size feet:

Well Type: EOR UIC Docket No.: E25885.3 Date/Time to Plug: 10/04/2001 11:00 AM
Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC
Proposal Rcvd. from: JAMES B. DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/04/2001 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

4 1/2" casing - squeezed 25 sxs 60/40 pozmix -10% gel with 400# hulls,
followed with 8 sxs gel, followed with 125 sxs cement.
Max. P.S.I. 700#.
8 5/8" S.P. - cement at surface.

Remarks: LEASE FORMERLY KNOWN AS PROBASCO 6-1. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

RECEIVED INVOICED Form CP-2/3

OCT 16 2001 DATE 10-16-01

KCC WICHITA INV. NO. 2002060810

OCT 11 2001

DIAMOND SHAMROCK
EXPLORATION COMPANY
P.O. BOX 400

#1 OMER ROY


9-7-20W
NE NE NE

AMARILLO, TX 79188-0001

CONTR BIG SPRINGS DRILLING CTY ROOKS

GEOLOG DAVE TENEYCK FIELD PROBASCO

ELV 2138 KB SPD 12/3/84 CARD ISSUED 3/7/85 IP P 62 BOPD, NW
2132 GL LKC 3504-3526 OA



SMP	Tops	Depth/Datum
SC	1693+ 445
OREAD	3263-1125
HEEB	3315-1177
TOR	3338-1200
LANS	3353-1215
BKC	3555-1417
ARB	3590-1452
RTD	3613-1475

API 15-163-22,527

8 5/8 " 328 / 225SX, 4 1/2 " 3612 / 200SX
NO CORES

DST (1) 3343-48 (TOR) / 30-60-30-60, REC 60' WM, 240' SW,
SIP 816-796#, FP 50-80 / 121-157#

DST (2) 3393-3465 (LKC) / 30-60-30-60, REC 250' SO SPKD
WM, SIP 856-786#, FP 70-101 / 121-131#

DST (3) 3517-67 (LKC) / 30-60-30-60, REC 30' CL OIL, 17'
HOCM (45% OIL, 55% M), SIP 334-293#, FP 20-20 / 30-30#

DST (4) 3596-3616 (ARB) / 30-60-15-30, REC 20' HOCM (40%
OIL, 60% M), SIP 151-394#, FP 20-20 / 40-40#

MICT - CO, PF (LKC) 3520-26 & 3504-10, W / 4 SPF, AC 2000G
(15% NE), SWB LD, GSO, SET 2 3/8 " TBG AT 3531, POP, P 62
BOPD, NW, 12/28/84

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS