


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-163-00996-00-00

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks County, Sec. 8 Twp. 7S Rge. 20 (X) W (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner Fred B. Anschutz  
Lease Name Loeffler Well No. 1  
Office Address 709 Union National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed April 20 19 56  
Application for plugging filed April 20 19 56  
Application for plugging approved April 21 19 56  
Plugging commenced April 27 19 56  
Plugging completed April 27 19 56  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	200'	
				5-1/2"	3678 1/2'	2928' 3"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand to 3520. Dumped 4 sacks cement with bailer. Filled hole with mud to 210'. Set 10 foot rock bridge with 15 sacks cement. Set top rock bridge at 40' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bill Hay Drilling Co.  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Wilma V. Brokes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilma V. Brokes  
709 Union Nat'l Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 56

My commission expires April 27, 1959

RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public.

PLUGGING  
FILED SEC 8 T 7 R 20W  
BOOK PAGE 57 LINE 36

MAY 11 1956  
05-0-1956  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-00996-00-00

ROTARY DRILLING LOG

OPERATOR: Fred B. Anschutz  
Loeffler #1  
SW SW NW Sec. 8-7S-20W,  
Rooks County, Kansas

CONTRACTOR: Prime Drilling Company  
COMM: 3/24/56  
COMP: 4/6/56

Remarks: Set 8-5/8" surface casing  
at 200' cemented with 150 sacks bulk  
cement, 2 sacks C. C.

Formations:

Surface Clay	40'
Shale Sand	200'
Sandy Shale	255'
Shale	560'
Shale & Shell	960'
Sand	1090'
Shale & Shell	1215'
Shale Sand	1700'
Anhydrite	1734'
Shale-Shells	2405'
Lime & Shale	2700'
Shale Shells & Lime	2770'
Shale & Lime	2840'
Shale	2960'
Shale & Lime	3280'
Lime	3622'
Dolomite	3635'
Arbuckle Lime	3650'
Lime & Shale	3680'
Rotary Total Depth	3680'

DECEIVED  
APR 11 1956  
ANSCHUTZ DRILLING CO.

Set 5-1/2" oil string casing at  
3678-1/2' cemented with 100 sacks  
cement.

We certify the above log is true  
and correct to the best of our  
knowledge and belief.

PRIME DRILLING COMPANY

*R. R. McNicol*

R. R. McNicol

PLUGGING  
FILE SEC 8 T 7 R 20W  
BOOK PAGE 57 LINE 36

RECORDED  
INDEXED  
APR 11 1956  
KANSAS