


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS County. Sec. 7 Twp. 7S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner BRADEN DRILLING COMPANY
Lease Name LEOFFLER Well No. 1
Office Address 1206 Union Nat'l Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed December 31, 1964
Application for plugging filed December 31, 1964
Application for plugging approved December 31, 1964
Plugging commenced December 31, 1964
Plugging completed December 31, at 11:30 p.m., 1964
Reason for abandonment of well or producing formation DRY HOLE

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3722 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
Sand & Shale	Surface Casing	0-	208'	8-5/8"	208'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: First plug - Filled hole up with heavy mud from 3722' to 500'. Pushed down plug with drill pipe & put 20 sx. cement thru drill pipe. Second plug - Filled with mud up to 200'. Put in plug, 1/4 sk. hulls, & 20 sx. cement thru drill pipe. Top plug - Mud to 40', 1/4 sk. hulls, & 10 sx. cement. Job completed: 12-31-64 - 11:30 p.m.

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1965
01-06-1965

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 1015 Wichita Plaza Bldg., Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
G. A. Hall

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

G. A. Hall

G. A. Hall, Prod. Supt.
Box 232, Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 1965

Henry Drey

Notary Public.

My commission expires 10-17-67

15-163-30003-00-00

BRADEN DRILLING COMPANY - Operator

SIERRA PETRO. CO., INC. - Contractor

LOEFFLER #1
C NE NW
Sec. 7-7S-20W
Rooks County, Kansas

T. D.: 3722'
Elev.: 2192' K.B.

Commenced: 12-23-64
Completed: 12-31-64

Casing:

8-5/8" Set at 208'

Cement:

with 150 sx. Common w/ HA-5

FORMATION

DEPTH

Sand & Shale
Shale
Sand & Shale
Sand
Shale & Shells
Shale & Lime
Anhydrite
Shale & Lime
Lime

208
480
1290
1510
1759
1787
1820
3270
3722

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1965

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

G. A. Hall
G. A. Hall, Prod. Supt.

Subscribed and sworn to before me this 4th day of January, 1965.

Lessee Dietz
Notary Public

My commission expires: 10-17-67