

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION NOV 16 2005 WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: D.R. Lauck Oil Company, Inc.

Address: P.O. Box 488/122 N. Main, Ellinwood, Ks. 67526

Phone: (620) 564-2013 Operator License #: 5427

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: November 6th, 2005 (Date)

by: Jerry Stapleton (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Depth to Top: 4320' Bottom: 4472' T.D. 4527'

API Number: 15 - 047-20,036 - 00 - 00

Lease Name: Julian "A"

Well Number: #1

Spot Location (QQQQ): - SW - NE - AAW

1650 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 15 Twp. 25 S S. R. 16 East West

County: Edwards County

Date Well Completed: 11/14/1968

Plugging Commenced: November 7, 2005

Plugging Completed: November 9, 2005

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Surface and Production data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

M.I.R.U. Sand off bottom at 4270' with 4 sacks cement. Moved casing jacks over well. Pulled slips out of head. Worked casing. Trip in hole with knife. Made 1st cut: 2000'; 2nd cut: 1600'. Got casing loose. Pulled 16 joints of 5-1/2" casing (1983.95'). Hooked up to casing. Put 50 sacks of cement at 1050'. Pulled up hole. Cement at 350'. Pulled up to 40' - 10 sacks cement. Pulled casing. Had more casing below 1600'. Pulled rest out. Trip in well with 2-3/8" tubing. Cement well with 100 sacks cement. Pulled tubing out, moved jacks off location, rigged down and moved off.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901

Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: D.R. Lauck Oil Company, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL Notary Public - State of Kansas My Appt. Expires 4/13/06

Signature of Edward S. Nemnich

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 15th day of November 20 05

Signature of Karen J. Mitchell Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten signature