

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Daystar Petroleum  
Address: 1321 W. 93rd St. N Valley Center, Ks. 67147-9136  
Phone: (620) 669-7391 Operator License #: 30931  
Type of Well: Oil Well Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: Nov 1, 2005 (Date)  
by: Dodge City (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Miss Depth to Top: 5275 Bottom: 5290 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-033-21406-0000  
Lease Name: Ransom  
Well Number: 16-1  
Spot Location (QQQQ): SW - SW - NE - NW 11/23/05  
1120 Feet from  North /  South Section Line R80MS  
1450 Feet from  East /  West Section Line CP2/3  
Sec. 16 Twp. 34 S. R. 19  East  West  
County: Comanche  
Date Well Completed: 11-05-04  
Plugging Commenced: 11-08-05  
Plugging Completed: 11-08-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Miss (Detrital)	oil and water	5275	5290	8-5/8	644'	none
				4-1/2	5419.83'	4424'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 5225', Spt 8 sks of cmt on CIBP. Shot Csg @ 4424. Pld 82 jts 41/2 to 1024'. Cir 63 bls of gelled water to load hole, pmp 40 sks of 60-40 poz with 6% gel. Pulled 8 jts 41/2 to 684'. Pmp 80 sks of 60-40 poz with 6% gel. Pulled 14 jts 41/2, took of csg head and ran 1 jt of csg to 40'. Pmp water to load hole then pmp 10 sks of 60-40 poz with 6% gel. Cmt to surface.

Witnessed by Jerry Stapleton with KCC at Dodge City

Name of Plugging Contractor: Plains Well Servicing License #: 4072  
Address: PO Box 346 Ness City, Ks. 67560-0346

Name of Party Responsible for Plugging Fees: Daystar Petroleum  
State of Kansas County, Rice, ss.

Donald W. Sanders Sr. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Donald W Sanders Sr.  
(Address) 150 East Forest Sterling, Kansas 67579

SUBSCRIBED and SWORN to before me this 16<sup>th</sup> day of November, 2005

**MARCIA DIASIO**  
Notary Public - State of Kansas  
My Appt. Expires 4/23/07

Marcia Diasio Notary Public My Commission Expires: 4/23/07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten signature]*