

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
07-01-1974
JUL 1 1974

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20528-00-00

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shields Oil Prod., Inc.

Complete Address Shields Bldg., Russell, Kansas

Lease Name Lesage Well No. 1

Location C SW SW Sec. 9 Twp. 7 Rge. (E) (W) 20

County Rooks Total Depth 3750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 11:45 A. Day 27 Month 6 Year 1974

The above well was plugged as follows:

RTD 3750' 8 5/8 csg set at 204' cwc 150 sk Cmt. Mat. 50-50 poz 6%

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe Heavy mud to 185' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/2/74

INV. NO. 9422-W