

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20474-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1973
04-02-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas

Lease Name Cecil Roy Well No. 1-V

Location 190' E of SW NE NW Sec. 8 Twp. 7 Rge. (E) (W) 20

County Rooks Total Depth 3715'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:30 A Day 29 Month 3 Year 1973

The above well was plugged as follows:

RTD 3715' 10 3/4 csg set at 233' cwc 200 sk Cmt. Mat. 50-50 poz W/6% total gel.

Drilled 9" hole to A/1850'.

Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 80 sk

cmt thru drill pipe. Heavy mud to 220' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 15 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red F. Murray
Well Plugging Supervisor

DATE 4/3/73

INV. NO. 7209-u