

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-163-00996-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SW NW

SEC. 8 TWP. 7 RGE. 20W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease W. Loeffler Loeffler

Operator Anschutz Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3678 Feet.

Plugging Contractor E & L Pipe Pulling

Plugging Contractor's License No. 249

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3677' with

100 sax cement behind - P. B. to 3560', perforated at 3539'

Filled with sand to 3520', set 4 sax cement with dump bailer,

pulled 2900' 5 1/2" - filled with mud to 200', set rock and 15

sax cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

E. J. [Signature]
District Conservation Agent

Date 4-27-56

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1956
04-30-1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 8 T 7 R 20W
BOOK PAGE 57 LINE 36 |