

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-00780-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1970
CONSERVATION DIVISION
Wichita, Kansas
07-20-1970

Operator's Full Name American Drilling Corporation

Complete Address 360 Sutton Place Wichita, Kansas 67202

Lease Name Western Auto Well No. 1

Location C SE SW Sec. 7 Twp. 7 Rge. (E) (W) 20

County Rooks Total Depth 3660'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co., Inc.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour Day 18th Month 7 Year 1970

The above well was plugged as follows:

Total Depth 3660' 8 5/8 csg set at 214' cwc

4 1/2 csg set at 3611' cw 100 sk cmt.

4 1/2 csg PBTD 3460 with top perf. (3400')

Set wood plug 3400' poured 10' sd, dumped 4 sk cmt W/dump bailer. (3350-3400)

Cutoff and recovered 700' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 12 sk gel W/2 sk hulls, 50 sk poz 6%, 8 sk

gel, plug and 50 sk poz 6%.

Gmt. (0-240) Gel (240-560) Gmt (560-800) gel (800-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/20/70

INV. NO. 2257-W

Signed: *Leo Manning*
Well Plugging Supervisor