

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23005-00-00
Spot: CSESWNE Sec/Twnshp/Rge: 25-7S-18W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: KU ENDOWMENT Well Number: 3
County: ROOKS Total Vertical Depth: 3480 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size 13.375 feet: 93 *113.10*
Surface Casing: Size 8.625 feet: 1140 425 SX CMT
Production: Size 5.5 feet: 3468 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/05/2002 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 727-3409

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 400# hulls.
Perfs 3249'-3254'; 3101'-3103'; 2984'-2986'.
CIBP 3442'.

Plugging Proposal Received By: CASE MORRIS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/05/2002 7:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 2908' w/5 sxs cement.
Shot 5 1/2" casing at 1518'. Pulled to 1440'.
Allied pumped 100 sxs with 300# hulls.
Pulled to 1150' - pumped 40 sxs with 100# hulls.
Pulled to 650' - pumped 30 sxs cement.
Pulled to 200' - cwc with 55 sxs cement.

DEC 11 2002
KCC WICHITA
12-11-2002

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Richard Williams*

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-12-02
INV. NO. 2003060930

DEC 10 2002

RIM OIL COMPANY
HAYS, KS 67601

25-07 -18W
SE SW NE

#3 K.U. ENDOWMENT

site: 1/2 S OF STOCKTON, KS

cty: ROOKS

API 15-163-23005

contr: EMPHASIS OIL OPERATIONS

field: RIFFE

geol: KENNETH VEHIGE

fr date 06/14/88 spd date 07/08/88 drlg comp 07/15/88 card issued 09/21/88 last revised 09/21/88

ELV: 1776 KB LOG	
tops.....	depth/datum
*DAK SD.....	465 +1311
*B/DAK SD.....	535 +1241
*CED HILL.....	660 +1116
*B/CED HILL.....	840 +936
ANH.....	1134 +642
B/ANH.....	1175 +601
TOP.....	2696 -920
HEEB.....	2903 -1127
TOR.....	2926 -1150
LANS.....	2946 -1170
MARM.....	3192 -1416
ARB.....	3236 -1460

IP status:

OIL, P 10 BOPD, NW, ARB 3250-3254 ,

PBTD.....3455 -1679

RTD.....3480 -1704

*DRILLER TOP

CSG: 13-3/8" COND AT 93 / 100 SX, 8-5/8" 1140 / 425 SX, 5-1/2" 3468 / 200 SX

NO CORES OR DSTS

MICT - CO, PF (ARB) 3250-3254, W / 4 SPF, AC 250 GAL (MA), SO, SET 2-7/8" TBG AT 3451, POP, P 10 BOPD, NW, 8/10/88

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS