

6010211

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22455-00-00

NW, SEC. 36, T 7 S, R 18 W/4
4290 N. From SE cor.
4620 W. From SE cor.
feet from N/S section line
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076
Operator: Black Diamond
Name & Address: 1105 E. 30
Hays Ks.

Lease Name Smith Well # 1
County Rooks
Well Total Depth 3380 109.85 feet
Conductor Pipe: Size 13 7/8 feet 91.88
Surface Casing: Size 8 7/8 feet 1236

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drlg. License Number 5665

Address Plainville Ks. 308 W. Mill

Company to plug at: Hour: 4 AM Day: 12 Month: 9 Year: 19 84

Plugging proposal received from Tom Alm

(company name) Pioneer Drlg. (phone) _____

were: order 185 sx. cem. 50/50 permix 6% gel. 3% c.c.

Heavy mud between plugs.

Pump cem. down drill pipe

Elev. 1820 Anhydrite. 1220.58 Arbuckle 3335

Dakota. 1450

370 Plugging Proposal Received by Dale F. Batthager (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:45 AM Day: 12 Month: 9 Year: 19 84

ACTUAL PLUGGING REPORT circ. @ 3340 for 30 mi.

25 sx @ 3340

40 sx @ 1240

100 sx @ 700

10 sx @ 40 on solid Bridge

10 sx in Rat Hole

Remarks: Allied Checked by Dennis Daniel

(If additional description is necessary, use BACK of this form.)

(did, did not) observe Part check. Invoiced

DATE 9-27-84 INV. NO. 3910

Signed Dale F. Batthager (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 9-24-84 SEP 24 1984

CONSERVATION DIVISION Wichita, Kansas