

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21, 838 ~~00-002~~

NE, Sec. 36, T 7 S, R 18 @/E  
990 feet from @/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Kansas "B" Well # 1

Operator: F & M Oil Co. Inc.  
Name &  
Address 422 Union Center,  
Wichita, Mo. 67202

County Rooks

Well Total Depth 3523' feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 1223'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Union Drilling Co. Inc. License Number 4

Address 422 Union Center, Wichita, Mo. 67202

Company to plug at: Hour: 8:00 AM Day: 19 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Loyl Lafon

(company name) Union Drilling Co., Inc. (phone) 316-262-2636

were: Order 180 sacks 50 permix - 4% cel. - 3% cel. cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3520' w/ 20 sbs. 2nd plug C 1324' w/ 100 sbs. 3rd plug C 300' w/ 40 sbs. 4th plug - solid bridge of bulls & plug C 40' w/ 10 sacks. Circulated 10 sacks in rat hole.

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 19:00 AM Day: 19 Month: 11 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 1223' cas. w/ 350 sbs common - 6% cel. - 3% cel. cl. & 125 sbs.

common - 2% cel. - 3% cel. cl. Ordered 180 sacks 50 permix - 4% cel. - 3% cel. cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3520' w/ 20 sbs. 2nd plug C 1324' w/ 100 sbs. 3rd plug C 300' w/ 40 sbs. 4th plug - solid bridge of bulls & plug C 40' w/ 10 sacks. Circulated 10 sbs in rat hole.

Remarks: drilled into backble

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1982  
CONSERVATION DIVISION  
Wichita, Kansas

11-22-82

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ did not observe this plugging.

INVOICED

12-20-82 Signed [Signature]  
1884-W (TECHNICIAN)